

SCIENTIFIC AMERICAN


[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1897, by Munn & Co.]

A WEEKLY JOURNAL OF PRACTICAL INFORMATION, ART, SCIENCE, MECHANICS, CHEMISTRY, AND MANUFACTURES.

Vol. LXXVII.—No. 17.
ESTABLISHED 1845.

NEW YORK, OCTOBER 23, 1897.

[\$3.00 A YEAR.
WEEKLY.]



THE MANUFACTURE OF STEEL TUBING—BLAST FURNACES OF THE NATIONAL TUBE WORKS COMPANY, McKEESPORT, PA.—[See p. 264.]

Scientific American.

ESTABLISHED 1845

MUNN & CO., - - - EDITORS AND PROPRIETORS.

PUBLISHED WEEKLY AT

No. 361 BROADWAY, - - NEW YORK.

TERMS FOR THE SCIENTIFIC AMERICAN.

(Established 1845.)

One copy, one year, for the U. S., Canada or Mexico.....\$3.00
 One copy, six months, for the U. S., Canada or Mexico..... 1.50
 One copy, one year, to any foreign country, postage prepaid, £0 16s. 5d. 4.00
 Remit by postal or express money order, or by bank draft or check.
 MUNN & CO., 361 Broadway, corner Franklin Street, New York.

The Scientific American Supplement

(Established 1876)

is a distinct paper from the SCIENTIFIC AMERICAN. THE SUPPLEMENT is issued weekly. Every number contains 16 octavo pages, uniform in size with SCIENTIFIC AMERICAN. Terms of subscription for SUPPLEMENT, \$5.00 a year, for the U. S., Canada or Mexico, \$6.00 a year, or £1 4s. 6d. to foreign countries belonging to the Postal Union. Single copies 10 cents. Sold by all newsdealers throughout the country. See prospectus, last page.
Combined Rates.—The SCIENTIFIC AMERICAN and SUPPLEMENT will be sent for one year, to one address in U. S., Canada or Mexico, on receipt of seven dollars. To foreign countries, eight dollars and fifty cents a year, or £1 14s. 11d., postage prepaid.

Building Edition of Scientific American.

(Established 1855.)

THE BUILDING EDITION OF THE SCIENTIFIC AMERICAN is a large and splendidly illustrated periodical, issued monthly, containing floor plans and perspective views pertaining to modern architecture. Each number is illustrated with beautiful plates, showing desirable dwellings, public buildings and architectural work in great variety. To architects, builders, and all who contemplate building this work is invaluable.
 Single copies 25 cents. By mail, to any part of the United States, Canada or Mexico, \$2.50 a year. To foreign countries, \$3.00 a year, or £0 12s. 4d. Combined rate for BUILDING EDITION with SCIENTIFIC AMERICAN, to one address, \$5.00 a year. To foreign countries, \$6.50 a year, or £1 6s. 9d. Combined rate for BUILDING EDITION, SCIENTIFIC AMERICAN, and SUPPLEMENT, \$9.00 a year. To foreign countries, \$11.00 a year, or £2 5s. 2d., postage prepaid.

Export Edition of the Scientific American

(Established 1878)

with which is incorporated "LA AMERICA CIENTIFICA E INDUSTRIAL," or Spanish edition of the SCIENTIFIC AMERICAN, published monthly, uniform in size and typography with the SCIENTIFIC AMERICAN. Every number contains about 100 pages, profusely illustrated. It is the finest scientific industrial export paper published. It circulates throughout Cuba, the West Indies, Mexico, Central and South America, Spain and Spanish possessions—wherever the Spanish language is spoken. THE SCIENTIFIC AMERICAN EXPORT EDITION has a large guaranteed circulation in all commercial places throughout the world. \$3.00 a year, or £0 12s. 4d., postpaid to any part of the world. Single copies, 25 cents.

MUNN & CO., Publishers, 361 Broadway, New York.

✉ The safest way to remit is by postal order, express money order, draft or bank check. Make all remittances payable to order of MUNN & CO.
 ✉ Readers are specially requested to notify the publishers in case of any failure, delay, or irregularity in receipt of papers.

NEW YORK, SATURDAY, OCTOBER 23, 1897.

Contents.

(Illustrated articles are marked with an asterisk.)

Acetylene gas explosion.....	253	Kelvin, Lord*.....	259
Airship crosses to France.....	257	Klondike, wealth of the.....	263
Archæological news.....	259	Lizards, color changes in.....	267
Bicycle, the chainless*.....	262	Mutoscope, Casler's*.....	260
Blast furnaces, great*.....	257	National Tube Works, the*.....	257
Boilers, thirty-six gas-fired*.....	265	Notes and queries.....	269
Books new.....	263	One loading for furnaces*.....	265
Camera, the Adlake hand*.....	264	Paeonian expedition, the.....	262
Car coupler law, the.....	267	Princeton.....	265
Cold, effects of, on life.....	268	Patent Office examinations of.....	267
Egypt, latest discovery in.....	266	Patents granted, weekly record.....	269
Electrical exhibition, N. Y.....	267	Power station, a great.....	258
Empress Queen, side wheel.....	261	Prison association exhibition.....	258
Engine, a large blowing*.....	255	Propelling device, auxiliary,.....	260
Engineers, the licensing of.....	258	Fryer's*.....	262
Fair of the American Institute.....	263	Railroad, the, in Alaska.....	260
Flue cleaner, rotary, Jones*.....	260	Shaft support, Stanley & Dar-.....	260
Fluorine, the liquefaction of.....	262	Shington's*.....	260
Furnace casting metal*.....	265	Steamer Cymric launched.....	263
Gas main stopper, Goodman's*.....	262	Steamer Empress Queen*.....	261
Governor and speed indicator,.....	260	Stove, Cowper hot blast.....	266
non-centrifugal*.....	260	Trolley ride, a long.....	268
Hose nozzle, Askins*.....	260	Tubing, steel, manufacture of*.....	268
Inventions recently patented.....	260	Yellow fever remedy, a.....	263
Iron, pig, removing from sand*.....	265		

TABLE OF CONTENTS OF

Scientific American Supplement

No. 1138.

For the Week Ending October 23, 1897.

Price 10 cents. For sale by all newsdealers.

I. ARCHÆOLOGY.—Recent Archæological Discoveries in the Nile Valley.....	PAGE 18196
II. CHARITABLE INSTITUTIONS.—The Braille School for the Blind at Saint Mandé.—A description of the methods of teaching children lessons and a trade.—5 illustrations.....	18194
III. CHEMISTRY.—Monazite.—By H. B. C. NITZE.....	18196
IV. ECONOMICS.—Japan and the United States Tariff.....	18193
V. ETHNOLOGY.—Primitive Transportation.—A most interesting lecture by Prof. OTIS T. MASON, giving an elaborate study of the methods of transportation among primitive and savage peoples.—18 illustrations.....	18190
VI. GEOGRAPHY.—Photography and Geography.—By A. E. MURRAY.—Notes on teaching geography by means of photography and the lantern.—2 illustrations.....	18193
VII. LOCOMOTIVE ENGINEERING.—A New French Locomotive.—A locomotive designed to move at a high speed by decreasing the end friction.—1 illustration.....	18187
VIII. MECHANICAL ENGINEERING.—The "Ruston" Oil Engine.—1 illustration.....	18187
IX. MECHANICS.—Perpetual Motion.—VII.—The completion of this important series of articles in which the classic form of perpetual motion apparatus are considered.—2 illustrations.....	18188
X. MEDICINE.—The Skin as a Diagnostic Factor in Disease.....	18198
Origin of Fat in the Body.....	18197
The Danger in Yellow Stigmata.....	18197
The Etiology of Yellow Fever.—By E. KLEIN, in Nature.....	18197
XI. METALLURGY.—The Development of the American Blooming Mill.—By RALPH CROOKER, JR.—A full article, giving the complete history of the blooming mill.....	18184
XII. MISCELLANEOUS.—The Louiton Float for Swimmers.—2 illustrations.....	18186
Engineering Notes.....	18189
Electrical Notes.....	18189
Miscellaneous Notes.....	18189
XIII. MUNICIPAL ENGINEERING.—The True Purpose of a Large Public Park.....	18186
XIV. NATURAL HISTORY.—The Colobus Vellerosus.—Description of the Silk Monkey.—1 illustration.....	18185
The Glow Worm and the X Rays.—3 illustrations.....	18194
The "Index Animalium".....	18194
XV. TRANSPORTATION.—Primitive Transportation.—18 illustrations.....	18190

THE LICENSING OF ENGINEERS.

Our attention has recently been called to a New York State law which seems to have been inspired less with a desire of serving the public and protecting its interests than for some less honest and less disinterested motive. We refer to a law enacted on May 22, 1897, establishing rules of qualifications for those having the care of boilers, steam generators or steam engines. Precaution should be taken to protect the public against accidents from negligence, ignorance or mismanagement; but the law in question can hardly commend itself to the unbiased mind, owing to the very narrow nature of certain of its features. The law is designed, not so much to enforce the employment of engineers for running elevators, boilers and engines in our large buildings, but it is designed to enforce the employment of a licensed engineer in small buildings, dwelling houses or apartment houses where steam heating apparatus is in use. To require a licensed engineer to take charge of apparatus of this kind is entirely unnecessary and oppressive. It is usual in such cases to have a fireman who is always in attendance and who is under the direct supervision of the janitor or the other manager of the building.

The particular features of this measure which show the animus which inspired the introduction of this bill are to be found in the qualifications governing the applicant for examination. In the first place, the applicant must be a citizen of the United States and over twenty-one years of age. The application must show that the applicant has been employed as a fireman, oiler or general assistant under a licensed engineer in some building in the city of New York for a period of not less than five years. It is evident from this provision that a thorough knowledge of steam engine practice is not what was sought after by the promoters of this bill. A thorough efficiency and a perfect familiarity with all the secrets and mysteries of steam engine practice are not sufficient to entitle the applicant to admission within the charmed circle, but he must "have been under the immediate supervision of a licensed engineer for a period of not less than five years," and, most wonderful of all, he must have been employed in the capacity of "fireman, oiler or general assistant in some building located within the city of New York." We are unable to grasp why this extraordinary limitation should be considered as an essential equipment for an engineer, but it is evident that the society who introduced and fostered this interesting measure believed that this was surely a clever means for advancing their own interests. The engineer who, perhaps, has been driving a locomotive for thirty or forty years would not be allowed to take charge of any steam heating apparatus in any building in New York, without first taking up his residence there and undergoing an apprenticeship of several years.

This bill, like many others of its class, was passed by the Legislature without proper investigation into its merits or demerits. The bill was introduced to benefit a particular class; it manifestly had no other aim or object. The protection of the public against mischief is entirely of secondary importance. Like much legislation that we have to endure, this tends to make many suffer for the benefit of the few. The enforcement of this unjust and foolish law will throw out of employment many who have, for years, had charge of buildings and who were competent to manage the same as well as if they "had been an assistant under a licensed engineer for a period of five years in some building in New York."

It is to be hoped that this foolish law will be repealed. If it is not repealed, it is probable its validity will be tested, and it is more than possible that the act will be deemed unconstitutional.

The interested motives of the promoters of this bill may be noted from the fact that it was to take effect immediately, the intent evidently being to throw hundreds out of employment before they would be able to qualify themselves for passing the required examinations, or even filing their applications therefor.

PRISON ASSOCIATION OF NEW YORK EXHIBITION.

The recent exhibition of the Prison Association of New York was held with the idea of giving the public a more intelligent idea of the inner workings of our State prisons than it can glean from the daily press. The objects of the association are practical and humanitarian, and this was evident from the character of the exhibits, in which was very little of a merely sensational character. By far the greater part of it consisted of specimens of the handiwork of convicts in the prisons of New York State. A notable exhibit was that of a complete set of furniture for the warden's office, made by the prisoners at Sing Sing. It was made in oak, richly carved and polished, and the work would have done credit to any first-class factory. In the same room was an inlaid box made of nine thousand three hundred and fifty-six separate pieces of wood and a banjo made of six thousand and fifty-one pieces, both being the work of inmates of Auburn prison. The work done by students in one of the art classes was represented by some grille work which showed excellent taste and skill.

The clothing worn by the convicts is made on looms in the prison, and the various State institutions for the blind, the deaf and other unfortunates are also entirely supplied from this source. Here were shown specimens of the various suits, both for men and women, together with prison-made blankets, toweling, etc. The various prison schools and workshops at Sing Sing were represented by drawings, cabinet and joiner work, plaster cornice work, boots, shoes and a host of other articles of wear and household use.

The one truly sensational object in the exhibition was the chair used in electrocution at Sing Sing, in which thirteen people have already suffered death. Except for the heavy straps at the arms and legs, there was nothing to suggest its tragic purpose. The celebrated Bertillon system for the identification of criminals was shown and explained, and a typical case of photographs from the rogues' gallery formed part of the exhibit.

In a room devoted to the Elmira Reformatory a surprisingly large number of the arts was represented by specimens of steel engraving, zinc etching, bookbinding, printing, photography, etc., done by the boys in the various classes. Near by was a large board of drawings, mechanical and architectural, which had been made by prisoners who had received only six months' instruction.

In looking over the varied collection of articles, all the results of instruction in useful arts and sciences, one found it difficult to believe that it had come from within the inclosure of State prison walls. The exhibition testified to the great advance which has been made over the old methods in the treatment of convicts, and it is easy to see that, as far as the occupations of prison life are concerned, everything is done to improve the more debased and ignorant among the convicts and give them some reasonable hope of honest livelihood when their terms have expired.

The inmates of the State Penitentiary for the Eastern District of Pennsylvania were represented by a large model of that famous institution, made by themselves. This prison is conducted on the much discussed plan of solitary confinement adopted generations ago by that State. The prison is laid out so that the idea of solitary individual confinement shall be literally carried out. Formerly, from the time the convict entered the massive gate of the prison to the day on which he left it he never spoke to or looked upon the face of any man but his keeper. To secure this result the prison is built on a radial plan. The outer wall of the inclosure is 30 feet high and 640 feet square. In the center of the square is a tower 40 feet in diameter and two stories high, and from this radiate, like the spokes of a wheel, eleven long, low, one-storied structures. Each wing is built with two outer walls and a central dividing wall and covered with a low pitched roof, and it is divided by partition walls into a long double line of cells. Each cell opens out onto a little yard which is surrounded by high walls and is of about the same area as the cell. Light is obtained by a grated window in the roof. Formerly the convict ate, slept and worked in his cell and took exercise in his little yard, absolutely alone. The prisoner is received in the central tower, his pedigree is taken, and he is then taken to one of the cells, which he never leaves except for exercise. The idea of solitary confinement is not carried out so literally as it formerly was; but the convict does all his work in his cell and is never thrown in contact with the other convicts in workshops and classrooms.

Very different from this is the modern steel prison, with its modern provisions for light, heat and ventilation. The methods of this construction were shown by illustrations of the new wing of three hundred cells which is being built at one of the State penitentiaries.

A SEVENTY THOUSAND HORSE POWER CENTRAL STATION.

Work is progressing upon a building in New York City which will contain the largest aggregation of motive power ever gathered together in a single plant. Hitherto that distinction has belonged to the great ocean steamships, the largest power at present being in the engine rooms of the Campania and Lucania, of the Cunard line, each of which is credited with a maximum trial horse power of 33,000. In this connection it is interesting to note that the huge industrial establishments to be found in the textile and iron industries, with their miles of shafting, their vast power-driven machinery and their employes numbered by the thousand, do not call for one-half the motive power that is to be found snugly stowed away in the engine room of a St. Paul, a Lucania, or a Kaiser Wilhelm der Grosse.

The new power house is being built by the Metropolitan Street Railway Company of New York and it forms part of the scheme for introducing electric traction on the whole of the 218 miles of street railways owned or controlled by this company. At present there are three different systems at work: the cable, the underground trolley and the horse car. The mechanical power is supplied from four power houses: a cable power house on Houston Street and Broadway, another at Fiftieth Street, a third on East Twenty-sixth

Street, and an electrical power station at 146th Street. The first three of these furnish power for the Broadway and the Lexington Avenue cable roads, and the last furnishes current for the Lenox Avenue underground trolley.

Work is now well advanced on the 55 miles of horse car lines which are being equipped with the underground trolley, and for the present the necessary electrical power will be furnished from the 146th Street and East Twenty-sixth Street stations, the generating capacity of the former station being increased and a new electrical equipment being added at the East Twenty-sixth Street station.

The many advantages to be gained by operating the whole of their vast system by one method of traction, and the uniformly good results which have been obtained on the experimental electric line on Lenox Avenue, have determined the company to make arrangements for equipping the whole 218 miles with the underground trolley. The advantages of economy to be gained by concentrating the power plant at one great central station are many and obvious, and it is this consideration that has led to the planning of the monumental power station which is now under construction near the East River between Ninety-fifth and Ninety-sixth Streets.

The economical distribution of current from one central station will be rendered possible by the use of a high potential in place of the 550 volt distribution which characterized the practice of a few years ago.

The building will cover a site measuring 201 feet by 270 feet. The foundation will consist of 8,000 piles, upon which will rest a five foot bed of concrete, which will extend over the whole area of the site. The building will be divided by a central wall into a boiler house and an engine room. The former will be four stories, and the latter two stories in height. The three lower stories of the boiler house will contain 87 water tube boilers, with a maximum capacity of 800 horse power each, and arrangements will be made for the use of forced draught. The upper third of the boiler house will be devoted to a set of huge storage bins, with a combined capacity of 9,000 tons of coal. The coal will be transferred from barges at the adjoining river dock to the bins by a system of elevators, and the ashes will be returned to the river scows by the same means.

In the adjoining engine room will be eleven cross compound condensing engines. They will be of the vertical type, and each will have a maximum capacity of 6,600 horse power. They will stand in two rows parallel with the dividing wall of the power house and each will be direct connected to a 3-phase alternating current generator. The current at 6,000 volts will be led to substations where static and rotary transformers will convert it to the 550 volt current used in the conduits.

We are informed by President Vreeland that the estimated time of construction is twelve months. The whole equipment will not, of course, be put in at once, but it will be set up contemporaneously with the demand created by the ultimate extension of the underground trolley to the Broadway and Lexington Avenue cable roads and to the various horse car lines owned or controlled by the company.


LORD KELVIN.

Among the distinguished scientists who attended the recent meeting of the British Association at Toronto, Canada, were Sir John Evans, Lord Lister and Lord Kelvin, each great in a different line of work. Lord Kelvin is particularly notable, owing to the fact that he has been a professor for over fifty years, and during this time he has witnessed the wonderful progress in physics and chemistry to which his personal contribution is so important.

Lord Kelvin, though of Scotch descent, was born in Belfast, in 1824, and was so precocious that he, then plain William Thomson, entered the College of the University of Glasgow at the age of twelve. From Glasgow William Thomson went to St. Peter's College, Cambridge, and in 1845 he graduated with highest honors and was elected a fellow of his college. Even before his Glasgow student days came to an end, William Thomson's original work in science was commenced, and his first mathematical papers, written before he entered Cambridge as an undergraduate, are all worthy of attention. From 1842 to 1845 he published important papers on heat, electricity and mathematics. In 1846 Thomson was elected professor of natural philosophy in the University of Glasgow, and thus at the early age of twenty-two he was appointed to the chair which he still holds. Many offers have been made him by the great English universities, but he has preferred to remain in his northern professorship, and his constancy is appreciated by the university which he adorns. The dynamical theory of heat early engaged the attention of Thomson,

and he published important papers upon the subject in 1849, and in 1852 more than one joint paper was undertaken by the life-long friends Joule and Thomson. In 1855, Thomson published a paper on "Electrodynamic Qualities of Metal," and it was while engaged in experimental work connected with this research that he began to make use of the assistance of his students; and this was the commencement of the physical laboratory of the University of Glasgow, which was, in fact, the first of physical laboratories. In 1855 and 1856 a new field opened itself to the genius of Thomson.

The problem of ocean telegraphy had presented itself to the world, and very soon he was practically called upon to solve it. When the cable was completed it was found that it required one minute to transmit one word over the cable. Thomson, experimenting with the reflection of the image of a candle thrown from his concave eyeglass on a sheet of white paper in a fairly lighted room, judged that the flame of a paraffine lamp reflected from a silvered mirror of one-tenth of that area would give an image bright enough for conveniently reading telegraphic signals. The mirror galvanometer was supplied for the 1858 cable. The directors of the Atlantic Company insisted that Thomson should go to sea with the expedition and also that he should take a patent for his instruments. To take out a patent was somewhat against his wishes, as he desired to give to the public the fruit of his labors, as he did with his sounding machine and his mariner's com-



LORD KELVIN.

pass, but he found in each case that the only way to secure attention to inventions of importance was to patent them and work the patents. In 1867 the siphon recorder was invented and patented. On the successful completion of the Atlantic cable, in 1866, he received the honor of knighthood.

Sir William Thomson's other inventions can be only briefly referred to. They include electrical test instruments and the improved mariner's compass, to say nothing of the large number of minor inventions. Sir William Thomson succeeded Sir George Gabriel Stokes, Bart., as president of the Royal Society, in 1890, and was created first Lord Kelvin in 1892. The degree of LL.D. was conferred on him successively by the Universities of Dublin, Cambridge and Edinburgh, and that of D.C.L. by Oxford. He was a fellow of both the London and Edinburgh Royal Societies, and has been president of the British and other associations. He has also received various decorations from abroad. He is Grand Officer of the Legion of Honor, commander of the Order of Leopold, and has received the German Ordre pour le Merite. He is a member of a large number of foreign societies and has a multitude of medals conferred upon him for his eminent inventions and discoveries.

In 1876 Sir William Thomson was a judge at the Centennial Exhibition at Philadelphia, and in 1884 he visited America to attend the Montreal meeting of the British Association. On this occasion he delivered a course of lectures on "Molecular Dynamics," at Baltimore, to a class composed mainly of professors from different parts of the world, gathered together at the Johns Hopkins University.

During Lord Kelvin's present visit to the United States he traveled quite extensively and made a num-

ber of addresses. On September 23, accompanied by Lady Kelvin, Count di Brazza Savorgnan, Prof. Elihu Thomson and others, he visited the Schenectady works of the General Electric Company. The electric railway work most arrested his attention. He was particularly interested in the new "surface contact" electric road, of the type now being constructed for Monte Carlo. Another feature of railroad work shown was the handling of one of the cars equipped for the South Side Elevated, of Chicago, weighing 25 tons and carrying four 50 horse power motors underneath.

With these cars the rate of acceleration obtained is as much as 40 miles an hour in 15 seconds, giving a tremendous increase in quickness of service on elevated or suburban lines.

Lord Kelvin was much interested in the experiments which were shown him in high voltage currents. He carried a little green note book with him in which he jotted down formulæ, figures and autographs. It was easy to see in so much advance he was glad to recognize here, in America, the rapid fruition of ideas and suggestions which the slow pace of European advance would not have allowed him to test on this large and satisfying scale.

Coming away from the works, his indefatigability as an investigator was shown by his leaving a comfortable carriage to ride in a dusty trolley car equipped with magnetic brakes. Emergency stops were made along the road quite frequently, and Lord Kelvin hung over the open trap door of the car floor with an interest that might easily have resulted in his disappearance down it, but for the restraining hands of those who wished him to go back to Glasgow University safe and sound.

The recent awards to this country of important electric railway contracts for England and the Continent have awakened great interest among English electrical engineers, who see in these contracts a source of danger to the British electrical industry.

Lord Kelvin was asked by The Evening Post representative as to his views on this matter. He said: "I do not consider it out of the way or surprising that these orders should be placed here. England has not yet developed her electric railway work to as large an extent as you have, and hence is buying, as she always does, in the best market to save money. She has the engineering and manufacturing talent, but lacks the opportunity. Here you have towns of 10,000 population springing up in a year, and they naturally want the latest and best, making a good demand which renders easy production on a large scale and also stimulates the older communities near them. We have no such developments in England, and the areas of our towns are smaller, so that the necessity of city transportation is not so keenly felt as with you."

Asked as to the near outlook in England, Lord Kelvin said: "The predictions as to the resort in this country to electricity on steam roads in some parts of the country seem to me well founded. From my observation I do not expect, however, any change at present by our big railroad systems in England. They move slowly and with judgment, and things must be proved. I do believe that all our English tramways and all our city travel must soon become electrical. I do not see any alternative from that."

Archæological News.

F. Petrie, Honorary Secretary of the Victoria Institute, England, writes to the Rev. Alfred Putnam, D.D., President of the Danvers Historical Society, a letter in which he says: "It will interest you to hear that one of the Institute members writes home from upper Egypt to announce his discovery of a palace of Pharaoh of the sixth dynasty, with numerous valuable inscriptions. The wine jars of Pharaoh were found intact in a long cellar. All were hermetically sealed, but, on breaking the seals of one, the wine seemed petrified."


With the present year, the Archæological Institute of America will begin the uniform and regular publication of its papers, reports and other documents in a new periodical which will be styled the American Journal of Archæology, second series. The journal of the Archæological Institute of America will be conducted by an editorial board, the members of which will represent the several interests of the institute and the institutions in its care. The new journal will succeed the American Journal of Archæology, and the new periodical will be issued six times a year. It will include the archæological papers of the institute, the papers of the American School of Classical Studies at Athens; papers of the American School of Classical Studies in Rome; proceedings of the institute and other archæological societies; reports of the institute; summaries of archæological news, correspondence, notes and notices. The journal will be published in England and America by the Macmillan Company.

RECENT INVENTIONS.

We represent herewith some recently patented inventions which seem to have considerable interest.

MUTOSCOPE.—One of the simplest forms of mutoscope is shown in the engraving. It is the invention of H. Casler, of Canastota, New York.


It is designed to show a series of pictures in rapid



H. CASLER—MUTOSCOPE.

succession, so as to produce the motions of living objects. The mutoscope consists of a receptacle having an opening in its face and a sliding rack mounted therein; a series of picture cards carried by the rack, a handle for reciprocating the rack, and a finger for momentarily retarding the upper end of the passing card.

SUPPORTER FOR ROTATING SHAFTS.—A novel de-



W. STANLEY & F. DARLINGTON—MEANS FOR SUPPORTING ROTATING SHAFTS.

vice for supporting rotating shafts has been patented by W. Stanley and F. Darlington, of Pittsfield, Mass.

Although this device is intended chiefly for delicate instruments, such as electric meters, it may be applied to other machinery. The vertical shaft is provided with two series of collars, which are placed within magnetic pole pieces having interior rings or flanges closely surrounding but not touching the collars on the shaft. The magnets which are joined to the pole pieces are arranged to produce consequent poles. The shaft is guided by small journals at the upper and lower ends. In consequence of this construction the shaft is supported without friction or wear.

NON-CENTRIFUGAL GOVERNOR AND SPEED INDICATOR.—In the governor shown, the speed of the engine to be governed is transmitted through a gear wheel, revolving coincident with the motion of the engine, to a movable worm gear, the position of which is controlled by the tension of a spring and the resistance of revolving fans. The result of this combination is that a constant increased or decreased motion will not be transmitted instantly or necessarily at all to the fans, for the action of the gear wheel upon the worms is twofold. It may drive the worm at a speed depending upon the relation of the pitch of the worm to the teeth of the gear, or, if motion be suddenly increased, the teeth will not follow the spiral of the worm when driving the worm, but the worm will be suddenly raised

one or more teeth, owing to the sudden increase in the speed of the driving mechanism. The raising of the worm does not, however, revolve it, but compresses the governing spring. It is this function which is utilized in determining the speed of the governed engine. Ultimately the increased speed of the engine, if not arrested by the governing mechanism, would communicate itself to the revolving fan. This would occur when the spring had resumed its normal tension; but this tendency of increase in the revolution under these conditions is counteracted in the fan itself, which is constructed so as to oppose an increasing resistance to any tendency to drive it faster or a decreased resistance to any tendency to drive it slowly.


When the worm revolves faster than a predetermined rate, the increased speed of the engine will be taken up first by the raising of the worm and then by the increased resistance to rotation of the fans. The worm being connected to the throttle valve of the engine, the first result of an increased speed of the governor will be a coincident movement of the devices for controlling the flow of steam. The contrary result would be accomplished provided the fan were driven at a less velocity.

J. F. Raders, of Flushing, N. Y., is the inventor of this governor.

AUXILIARY PROPELLER.—The engraving shows a simple and apparently efficient device for propelling and steering a vessel in case the ordinary machinery becomes disabled or in case a sailing vessel requires auxiliary or alternative propelling or steering machinery.

The motor case has conical ends and is provided with a motor, either electric, steam or air, and a screw driven by the motor. The motor case has a hollow arm which prevents it from turning, and which contains the electric wires or the steam or air pipes connected with the motor. The braces serve to hold the case in the position of use.

It can readily be imagined that a device of this kind might prove a very useful adjunct to a steamship, large sailing vessel, or even a war vessel.



R. M. FRYER—AUXILIARY PROPELLING DEVICE.

R. M. Fryer, of Washington, D. C., is the inventor of this propeller.

HOSE NOZZLE.—The engraving shows an improved hose nozzle which may be made to throw a solid, round stream or a divergent, fan-shaped stream at will.

The nozzle body is a single casting, with a circular delivery and a flattened delivery, both extending in practically the same direction. A valve plug is fitted to the nozzle body, at the junction of the two deliveries, so that, by turning the plug in one direction or the other, the water may be directed so as to pass through the cylindrical or circular nozzle.

This device is the invention of J. Askins, of Redfield, N. J.


ROTARY FLUE CLEANER.—L. J. Jones, of East Norwalk, Conn., is the inventor of a rotary flue cleaner, designed to loosen soot, ashes and scale, and at the same time force them out of the flue.

The cleaner consists of a case provided with steam ports, a turbine wheel placed in the casing, mounted on a shaft and capable of revolving with great velocity, and a pair of scrapers pivoted to a cross arm on the shaft and arranged to be thrown outward into contact with the flue by centrifugal force. A tubular handle, attached to the casing, serves as a conduit for steam supplied to the turbine.

PERSONS in New York may now talk with Council Bluffs, connections just having been completed.


A Statue of Tubal Cain.

The iron and steel manufacturers of eastern Pennsylvania have decided to erect a statue to Tubal Cain, the




L. J. JONES—ROTARY FLUE CLEANER.

original worker in metals, as their patron. They propose to honor his memory by erecting a statue on the Ohio River, at the junction of the Allegheny and Monongahela Rivers. The project has been taken up by the Engineers' Society of Western Pennsylvania and the Pittsburgh Foundrymen's Association. It is proposed to build the pedestal of the statue of iron and steel, at a



J. F. RADERS—NON-CENTRIFUGAL GOVERNOR AND SPEED INDICATOR.



J. ASKINS—HOSE NOZZLE.

Nansen polar expedition. The famous explorer will sail at a later date. A number of the larger articles used on the famous voyage of the Fram are now on exhibition at the Stockholm Exposition and will be forwarded in a short time. The collection which has already arrived in this country consists of various utensils fashioned for the most part by Nansen and Johannsen when they left the Fram and made a dash for the pole. Each article mutely tells the story of hardship, suffering and daring.

THE LARGEST AND FASTEST PADDLE STEAMER IN GREAT BRITAIN.

BY A. J. SINCLAIR.

We present two engravings—an exterior and an interior view—of the new steel paddle steamer "Empress Queen," which is the largest and fastest paddle steamer in Great Britain and which has just recently been completed by the Fairfield Ship-building and Engineering Company, Govan, near Glasgow, to the order of the Isle of Man Steam Packet Company, Limited, Douglas, Isle of Man, for their passenger and mail service between Liverpool and Douglas (a distance of 70 nautical miles). The first vessel owned by the Isle of Man Steam Packet Company, which have now a fleet of a dozen steamers—8 paddle and 4 twin screw steamers—was built in 1830. It was of 116 tons burden and 200 indicated horse power.

It was through the kind offices of Lord Henniker (Governor of the Isle of Man) that the Steam Packet Company secured the consent of Her Majesty Queen Victoria to have the ship called after her own name. The principal dimensions of the "Empress Queen" are: Length over all 375 feet, breadth of hull 42 feet, breadth over paddle boxes 83

feet 6 inches, and moulded depth is 25½ feet. She is constructed of steel throughout and is of 2,500 gross tons. The hull is divided into several watertight compartments by means of steel transverse bulkheads, which, besides reducing the risk of foundering to a minimum, materially augment the strength of the structure, forming valuable supports and ties between the decks and framing. The decks are four in number, and are termed "lower," "main," "spar," and "promenade." The dining saloon, on the lower deck, accommodates 124 first class passengers, and is the handsomest saloon of its kind of any Channel steamer afloat. Ample accommodation is provided for the number stated to dine at one time, and in addition to the long tables running along the full length of the room, there are several small tables at which parties can

dine. The ceiling of the saloon is in white and gold. Forward of this are the pantry, scullery and plate-room.

The pantry is furnished with all the latest appliances, including steam, hot water boiler and steam carving tables.

Another good feature is the fact that there is a saloon galley connected with the saloon pantry, where

saloon, which is unique in form and decoration, the latter being in satinwood, and set off in cozy alcoves by means of carved and arched columns in the same kind of wood. It is upholstered in an electric blue shade of velvet, with Axminster carpets to match. Leaving the main saloon, a descent is made by a handsome staircase to the second general saloon, which is fitted up with mahogany and satinwood panels, and upholstered in a light shade of mouquette velvet, with carpets to match.

The forward part of the ship is allotted to the second class passengers. The dining saloon, forward of the machinery space on the lower deck, having bar and pantry adjoining, provides ample room for the second class passengers. On the same deck and forward of this, is a ladies' second class saloon, supplied with every up-to-date requisite.

On the main deck above is arranged a second class shelter, which contains a bar, buffet, mail and parcel rooms. The gentlemen's sanitary appointments are of the most modern system, and are provided for first and second passengers, abaft and forward of the sponsons respectively.

On the spar deck aft, in houses, are six handsome private cabins, fitted with berths, etc., and

amidships on the same deck is a cloak room, and combined bar and smoking room, while all fore and aft all available space is utilized for sitting room, there being sparred seats sufficient to seat over 600 persons.


Above this is a very spacious promenade deck extending from the fore end of the boiler room aft to the end of the first class cabin, with buoyant seats running the entire length, excepting a small portion at the after end, which is appropriated for the stowage of boats, a feature which has received special attention, so as to allow of the immediate launching of the boats if necessary.

The bridges (36 feet above the water line) that surmount the promenade deck are placed one at the foremost extremity for navigating purposes, and the other between the funnels, and extending from sponson to



MAIN SALOON, LOOKING FORWARD.

everything may be sent down without carrying the edibles through the saloon, as in the older boats. The first class smoke-room is large and agreeably arranged, the framing being in oak, the paneling in teak, and the upholstery in dark green morocco, while white and gold are the prevailing colors of the ceiling. The main saloon, which we illustrate, is paneled in mahogany, inlaid with satinwood and ebony, while the ceiling is chastely decorated in white and gold. All the upholstery is done in the finest mouquette velvet, while the carpets are of the best Axminster, and form a beautiful contrast in shade with the cushions. The saloon is provided with couches, writing tables, etc., which go to make it as comfortable and complete as the most fastidious members of the traveling public could desire. To the right of the main saloon is the ladies' special



THE ISLE OF MAN STEAM PACKET STEAMER "EMPRESS QUEEN."

sponson, with captain's house under, for the better handling while docking and taking piers. From both of these bridges the bow and stern rudders are controlled by means of wheels connected with independent steam-steering gear placed below on the engine starting platform. A hand-screw steering apparatus is also placed in reserve aft in case of emergency. Docking and engine telegraphs are provided on each of the bridges.

The vessel was engined by the builders and the machinery consists of compound diagonal surface-condensing engines, the diameters of the cylinders being one 68 inches and two 92 inches in diameter, with a piston stroke of 84 inches. They are the largest and most powerful paddle-wheel engines yet built. Their nominal and indicated horse powers are respectively 1,290 and 10,000. When the ship was on her trials they worked up to close upon 12,000 horse power.

The three steam cylinders are placed side by side, and working on three cranks, the high-pressure cylinder being placed between the two low-pressure cylinders. The high-pressure cylinder is fitted with a piston valve and each of the low-pressure cylinders with flat slide valves, all controlled by the usual double eccentrics and link motion valve gear. The crank shaft is a ponderous piece of machinery. It is built, and, together with the paddle shafts, is forged of mild steel and bored hollow. The starting and reversing is effected by a large steam and hydraulic engine on the direct-acting principle.

The condenser is cylindrical, and placed athwartships between the cylinders and the supports for the shafting, and the condensing water is supplied by a circulating pump worked by an independent steam engine.

The paddle wheels are made of steel, and constructed on the feathering principle, with curved floats. The floats are each 18 feet in length. Steam is supplied to the engine by four double-ended boilers arranged in two compartments, one forward and one aft of the engine room. They are adapted to work with Messrs Howden's system of forced draught.

The vessel has two funnels and two pole masts, and presents a very handsome and majestic appearance. On July 8, the "Empress Queen" made four trial runs between the Cloch and Cumbræ Lights, when she averaged over 22 knots per hour, and, considering the stormy weather which prevailed on that day, the result was gratifying. The following Monday a six hours' sea trial was carried out on the Clyde with equal success, the average speed over the whole course out to sea being 22 knots. While on her trials on the Clyde the highest speed attained was fractionally less than 23 knots an hour.


The "Empress Queen," which is licensed to carry 1,994 first and second class passengers by the Board of Trade, is now running to and from Liverpool and Douglas, which will be her regular station.

The Railroad in Alaska.

The building of a railroad through Chilkoot Pass will be undertaken by the Chilkoot Railroad and Transportation Company, of Tacoma. It will be 8 miles long and will connect Dyea at tidewater with the mouth of the Dyea Cañon. Transportation through this cañon and across the pass to Crater Lake will be effected by a system of tramways, the contract for which has been awarded to the Trenton, N. J., Iron Company, which agrees to have them in operation by June 15, 1898. The tramway will be of the Bleichert system. The first one will be 4 miles in length, reaching from the cañon to Sheep Camp, with a rise of 1,000 feet. A second tramway will extend from Sheep Camp to Summit, $3\frac{1}{2}$ miles, with a rise of 2,500 feet, and thence to Crater Lake, with a fall of 500 feet. Iron supports will be put in every 100 feet. The tramway will have a capacity of 120 tons daily—sufficient for the outfits of 200 miners. It is to be hoped that the promoters of this much needed means of transportation will not encounter any serious legal difficulties. It was believed that the Interior Department had the power to grant permission to run over the public lands, but no provision was made in the act of March 3, 1875, for Alaska, as no one then thought that railroads would be run in the Territory. The same state of affairs applies to the tramways, the cable roads, the telegraph and telephone lines and other enterprises which demand passage over the public domains. The originators of the enterprises will be forced to apply to Congress for charters or for legislation that may enable the Interior Department to take charge of the matter. It is probable that Congress will act at once upon these applications, so that the railroads can be built before the spring season opens. The Interior Department has many applications for such franchises, but it can do nothing but refer them to Congress for action, and so notifies all those who applied. Out of the five passes over which routes could be constructed from the coast to the interior, three have been surveyed for this purpose.

A GAS MAIN STOPPER.

To temporarily stop a gas main and prevent the flow of gas therein, as is frequently necessary in making changes or repairs, the device shown in the accompanying illustration has been invented and patented by Patrick Goodman, 115th Street, East River (address in care of the Standard Gas Company), New York City. Fig. 1 shows the manner of using the device, a portion of the gas main being broken out, Fig. 2 represents a cross section and Fig. 3 illustrates the manner of inserting the device in a pipe. Two flat steel springs are made with eyes at their ends by which they are pivoted to two rods, one telescoping with the other, the springs being slightly curved outwardly, but being capable of compression. Outside of the springs is an elastic packing, which may be of rubber tubing, and outside of such pack-




GOODMAN'S GAS MAIN STOPPER.

ing, and inclosing it with the springs, is a casing to which is attached a flexible diaphragm of cloth, leather or other suitable material, practically impervious to gas. Pivotaly attached to the outer ends of the telescoping rods are outwardly extending handle bars, slightly curved near their pivotal points, and one handle bar being slightly longer than the other. The device, when first inserted in a hole in the side of a pipe or main, occupies an inclined position, as shown in full lines in Fig. 1, but, upon drawing upon the longer handle, the device assumes a vertical position, as indicated by the dotted lines, the springs being forced outward to form a ring which presses closely against the interior surface of the pipe, and, with the diaphragm, entirely shuts off the flow of gas.

THE CHAINLESS BICYCLE.

The most conspicuous bicycle exhibit at the American Institute Fair is that of the Bayvelgere machine—one of the new type of chainless wheels which is likely to compete strongly with the chain-driven type during the coming season. The exhibit is somewhat historical, as it contains one of the earliest bevel-gear wheels put upon the market and one or two of the experimental machines made by the Bayvelgere Company, among which is one that has several thousand miles travel to its credit and shows surprisingly little wear as the result of it.

The aim of the designer of this wheel has been to provide a construction which will maintain each pair of gears at all times in proper alignment and yet allow of considerable deflection in the connecting shaft. This has been accomplished by inclosing and supporting each pair of gears, both at the crank hanger and at the



DRIVING GEAR OF THE BAYVELGERE CHAINLESS BICYCLE.

rear wheel, in a rigid casing, which is incapable of being sprung out of shape by any rough usage that may be put upon the bicycle. The power is transmitted from one set of gears to the other by means of a shaft formed with a knuckle joint at each end.

Every wheelman is well aware that, under the strain of hill climbing, when the maximum pressure is put upon the pedals, the rear forks are liable to spring somewhat out of line. This is due to the pull of the chain being applied only on one side of the wheel. In the chain-driven wheel this flexibility is of comparatively little consequence; but any such distortion on a bevel-gear wheel, provided with a rigid intermediate shaft, would cause the gears to bind and set up a con-

siderable amount of friction. The flexible shaft shown in the accompanying engraving adjusts itself to this distortion or to any bending that may be produced by collision or other accident, and permits each pair of gears to work without binding, even though they be considerably out of line with each other.

The flexible shaft is provided with a four point knuckle joint at each end, the points consisting of steel balls which engage corresponding holes in the ends of the axles of the gears at the crank hanger and the rear hub. Each of the two gear wheels adjoining the intermediate shaft is formed in one with a short hollow axle, whose bearings are carried in a short threaded cylinder which is firmly screwed into the crank hanger or the housing of the rear gears, as the case may be. The two casings are connected by means of a tube with enlarged and threaded ends which just fills the space between the casings, and is held in place by means of threaded couplings. Wear of the intermediate gears is taken up by screwing the cylinders containing the ball races into the casings, and the ball bearings are adjusted by screwing up the cones on the outer ends of the short hollow shafts or axles.

The mechanism is entirely inclosed by the casings and connecting tube, and when it is filled with oil or other lubricant, it will run for months without attention. Taken altogether, it is a highly creditable piece of work, both in design and construction.

The Patagonian Expedition from Princeton University.

The Princeton Patagonian expedition which left in February, 1896, returned in August. It was under the auspices of Prof. W. B. Scott, of the department of geology. The object of the expedition was to collect vertebrate fossils from the tertiary deposits and the skins and skeletons of recent birds and mammals. The objective points, says Science, was the port of Gallegos, on the east coast of Southern Patagonia. From this point investigations were conducted along the coast from Sandy Point, in the Straits of Magellan, to Port Desire, on the north. In this region many interesting fossil forms were secured, and a nearly complete series of living birds, mammals and plants. After spending several months in the coast region, the expedition went into the interior, where many new glaciers and water-courses were discovered. Being an unexplored country, not only were new facts relating to the geography of the region discovered, but many plants and animals new to science were also collected, while the information obtained relating to geological phenomena was of the greatest value. Numerous volcanic cones hitherto unreported were discovered.

Owing to the difficulty of traveling in the interior, it was impossible to take any great supply of provisions. So it was found necessary to limit the expedition to Messrs. Hatcher and Peterson. They were absent five months on this trip, during which time it was impossible for them to receive or dispatch any mail and they did not meet with a single human being. After spending a little more than a year on the mainland, the expedition proceeded to Tierra del Fuego and the adjoining islands, where important collections were made and observations were taken of the geology and paleontology of the islands.

Throughout their work the Argentine government was very generous and courteous to the expedition, giving to its members transportation on its war vessels from Buenos Ayres to Gallegos and return, offering to place at its disposal a smaller vessel for use in researches among the islands. The collection is the most valuable of any formed from that region, including as it does a nearly complete series of mosses and flowering plants, 800 skins and skeletons of recent birds, eight tons of fossils, including more than 1,000 skulls and many nearly complete skeletons.

Further Experiments on the Liquefaction of Fluorine.

At the meeting of the Academy of Sciences at Paris, October 12, M. Moissan read a paper on the liquefaction of fluorine with Prof. Dewar's instruments in London. He said it retained its liquid form at minus 120 degrees Centigrade, whereas almost every chemical affinity of the most active of known gases disappears in such great cold. The exceptions are hydrogen and turpentine oil, which even in a temperature of minus 210 degrees Centigrade combine with fluorine and are incandescent.

SCIENCE announces the establishment in Switzerland of a weather bureau. It says: "A dispatch is sent each evening from Zurich giving the weather probabilities for the next twenty-four hours. The predictions are based on data received from the principal meteorological stations of Europe combined with experience of local conditions. The dispatch is further distributed by telephone to those communes prepared to subscribe ten francs [\$2] per month for the service."

The American Institute Fair.

In the basement of the Madison Square Garden will be found an exhibit which will be recognized by visitors who were present at the Chicago World's Fair and became familiar with the celebrated display in the Department of Forestry. Reference is made to the lovely collection of American woods shown by Romeyn B. Hough, B.A., of Lowville, N. Y. It was a happy inspiration which led Mr. Hough to conceive the idea of preserving his specimens in the form of extremely thin and transparent sections or shavings, instead of in the form of the blocks or thick strips with which we are familiar. The most unique part of this exhibit is a set of albums, each page of which contains three specimens of one particular kind of wood. The sections measure about 2 inches by $4\frac{1}{2}$ inches and they are cut from the tree in three different directions: transverse, radial and tangential. The wood is prepared by a process which in no way interferes with the natural colors and texture of the wood, and the specimens are cut in a special machine which produces sections varying from $\frac{1}{8}$ of an inch for transverse to $\frac{1}{16}$ of an inch for radial and tangential sections.

So fine is the work of the machine that sections of California white pine are shown which are only $\frac{1}{16}$ of an inch thick. These are of course transparent, and on holding up the hand to the light and looking at it through one of these sections a curious so-called X ray effect is produced, due to the refraction of the light in passing through the wood. In addition to the exquisite beauty of this work, the collection of volumes forms a complete treatise on the subject of American woods. The exhibit also includes preparations of woods for the stereopticon and the microscope, and a collection of wooden cross section cards for visiting or business purposes. The printing qualities of the wood, either for type or steel plate, appear to be excellent, and the grain and delicate tints of the woods give them a dainty and artistic effect.

The exhibit of the American Gas Furnace Company, of Elizabeth, N. J., comprises an oil gas machine placed in Machinery Hall, and in the Main Hall a large number of furnaces for hardening and annealing steel work, gas forges, brazing blowpipes, a furnace for automatic hardening, and an automatic tempering and coloring machine, in which the work is fed into a hopper and passes through a revolving spiral way, where it is constantly subjected to the action of sand or ground flint, heated to the proper degree, and finally leaves the furnace drawn to the desired temper-color.

The oil gas machine for converting naphtha into a fixed gas is automatic in its action, requiring no further attention than keeping the storage tanks filled. A 2 inch pipe is laid from the gas machine across the Garden to the floor above, and the mixture of atomized naphtha and dry air is so well combined that there is no evidence of condensation at any point. The gas is delivered to the furnaces at a pressure of 1 pound to the square inch. The lighting qualities of the gas are shown by means of a number of Welsbach lamps, to which it is fed through a pressure regulator, which reduces the gas pressure of 1 pound to the square inch required for the furnaces to 4 inches of water pressure. This is the first public exhibition made by this company, and its plant is certainly an interesting feature of the fair.

The Otto Gas Engine Company, of Philadelphia, show four of the justly celebrated Otto engines, the oldest type of gas engine to take a successful hold upon the public. Seven thousand of these engines are at work in England, and one of these shown at the fair is numbered 5,588, showing that over this number have been built in the United States. The exhibit comprises one 9 horse power horizontal engine, driving a 110 volt dynamo; a 25 horse power marine engine; a 36 horse power horizontal power engine and a $3\frac{1}{2}$ horse power vertical engine.

The Harting Gas Engine Company call attention to the few parts of their machines, rendering them easy to operate by the unskilled hands of the amateur. The governing is done from the exhaust, and the claim of simplicity is certainly borne out by the appearance of the $2\frac{1}{2}$, 1 and $\frac{3}{4}$ horse power engines exhibited.

Wietz & Weiss, of New York, show four gas engines, ranging from $\frac{1}{2}$ to 8 horse power, which they claim will develop a horse power hour on 17 cubic feet of gas, and 1 horse power and 2 horse power kerosene engines, which are said to burn but 1 pint of oil per horse power per hour. A closed oil tank, carrying sufficient oil to run the kerosene engine ten hours, is attached to the cylinder above the crank chamber. The oil is forced into the cylinder through a small tube, and there it is vaporized and mixed with the proper quantity of air. To control the engine under varying load, the number of injections is regulated by a governor connected to an eccentric on the main shaft.

An exhibit worthy of special mention is that of the Clauson-Kaas Manufacturing Company, of New York. The stall is filled with a varied assortment of the very beautiful papier maché models which are made by this company, chiefly for use in the lecture room. The different departments include models of fruits, vegetables, botanical specimens, the anatomy of the human body

and many other objects. The models are all hand painted, and the greatest care is taken to give them perfect shape and color. The imitation is carried to the point of weighting the objects, and the surface is made to give the correct sensations to the touch. This reproduction of the "feel" and weight in the case of fruits and vegetables is very deceptive, and it is difficult to realize that the weighted papier maché potato is not the garden-grown article. The most difficult and successful modeling is shown in the anatomical department, and the model of the human ear, in which each articulated detail is exactly reproduced, is a masterpiece of modeling. A curious display of models is that forming part of the mycological cabinet, which is the name given to the imitations of mushrooms and toadstools of all continents. The object of this cabinet is to propagate and enlarge people's knowledge of all edible and poisonous mushrooms and toadstools. It is considered that the surest way to teach the public what to gather and what to let alone is to teach them by means of these models and the description that goes with them. It may surprise the uninitiated to learn that the collection includes models of 119 specimens, of which 21 are poisonous, 14 suspicious, 24 not edible, the remainder—less than one-half of the total—being edible.

A modest stand, but one that should commend itself to every resident of the city that has the welfare of the dumb creation at heart, is that containing the Hallanan rubber horseshoe pads. The pads are made of rubber and canvas, backed with sole leather. They are made slightly larger than the horse's foot across the quarters, and form part of the shoe. The shoer fits the foot and pad with a three-quarter steel shoe of uniform thickness, and the space between the pad and the foot is filled with tar or oakum. The object of the pads is to place the weight of the horse evenly on the sole and frog and prevent the jar to the foot. It also tends to prevent slipping on smooth pavements or on ice-covered ground. It is used by the fire departments of New York and Brooklyn, where it is said to give good service and it has received the indorsement of several societies for the prevention of cruelty to animals.

One of the best pieces of mechanical construction in the Fair is an angular coupling or quarter turn countershaft, shown by T. R. Almond, of Brooklyn. It is intended to be used in place of the quarter turn belt or miter gears. At the point of intersection of the center lines of the two shafts, and at right angles to them, is a vertical shaft upon which is a stout sliding sleeve provided with two short horizontal arms placed 90 degrees apart. The arms terminate in steel balls which engage sockets on the extremities of two short rocking levers which are pivotally attached to the two countershafts. As the shafts are turned the sleeve on the vertical shaft has a rotating and sliding motion. The device, which is ingenious and well worked out, is said to develop less friction and show less wear than the more common methods of making quarter turn connections. The inventor was awarded the John Scott medal on the recommendation of the Franklin Institute.

A pair of electric dumbbells are shown by the W. and S. Electric Company, of Brooklyn. A small dry battery is suspended between the shoulders, and the wires are carried to the two dumbbells, where they connect with the wire wrapping of the handles. The strength of the current is regulated by a switch placed on the chest of the user.

The New York Trade School has contributed an exhibit of the excellent work turned out by its students, which calls for special mention. The question of trade schools and apprenticeship is a very live one just now, and if any one doubts the value of the instruction which is given in technical night schools, he should examine this exhibit. The work is shown on boards and comprises most of the departments. The work done by the class of 1896-97 in blacksmithing is exceedingly fine and much of it shows a finish which would do credit to a skilled journeyman. There are also exhibits of work in stone cutting, sheet metal work, steam fitting and plumbing.

The management have introduced some novel features in this year's exhibition, notably the food show and the exhibition of fruits and flowers. The latter is somewhat limited, but what there is of it is very choice, many of the exhibits coming from professional exhibitors, and from the gardens and conservatories of such exhibitors as Cornelius N. Bliss, William Rockefeller, J. Loeb and D. Wilson. The field is such a vast and attractive one that it should soon be possible for the annual exhibit of fruits and flowers to develop an independent existence. There is sufficient wealth and enthusiasm devoted to floriculture alone in and around Greater New York to fill the whole Garden with exhibits at an annual show.

A Remedy for Yellow Fever.

A special cable dispatch to the New York Sun, from Montevideo, on October 10, states that Dr. Sanarelli, the discoverer of the bacillus of yellow fever, announces that he has discovered a curative serum for that dread disease. He will shortly publish the results of his experiments.

Wealth of the Klondike.

The steamer City of Topeka arrived at Seattle, October 11, from Juneau, Alaska, bringing several miners from the Klondike regions and \$300,000 in gold. Among the passengers was John F. Maloney, of Juneau, who came out from Dawson City with the Galvin party. He stated that the previous accounts of the wealth of the Klondike were overestimated. He also stated that one claim would produce \$1,000,000, and that over \$2,000,000 would come out of the Klondike region this fall. Patrick Galvin, who is recognized as one of the bonanza kings of the Klondike and who has been engaged in mining for three years, said: "There are 461 claims which have been operated sufficiently to prove their richness. There are 280 claims staked out, but not developed. Taking these claims and figuring out their cubic contents and making a conservative estimate, I do not see why the output from these claims alone should fall short of \$50,000,000."

In a letter from Lake Lindermann a newspaper writer says that there is chaos on the Dyea trail. Thousands of people are struggling hopelessly on with damaged outfits and thousands with no outfits, clothes, food, or shelter are beating back against the storm, trying to reach Dyea. For eleven days the storm has raged, the wind blowing a gale and the rain falling in torrents. To the 800 or 900 people cooped up between the mountain lakes, high above the timber line, the past has been a nightmare. Baking powder is held at \$5 per pound; horseshoe nails being 25 cents each. One man at Crater Lake went back over the trail and gathered up 500 nails from the hoofs of dead horses and sold the lot to one man for \$65. A stick of dry wood the size of a man's arm sold readily for \$4, and green wood sold at the rate of \$1,000 a cord.

Libraries and Our New Supplement Catalogue.

It is gratifying to note that our new SUPPLEMENT Catalogue has been eagerly received by the large libraries of the country and has been placed on their shelves as a valuable work of reference. Many of the librarians have been so favorably impressed with the catalogue that they have wished additional copies for various departments of their libraries.

The librarian of the Wabash College Library says it is "An elaborate and most excellent index catalogue." The librarian of the Carnegie Library, of Pittsburg, says: "This little volume will get so much use in our library that we should like another copy, if you could spare one." The librarian of the Public Library, Peoria, Ill., says: "We shall find it of great value in reference work." The librarian of the Cornell College Library, Mount Vernon, Ia., says: "It will be of much help to us in using our back volumes of the SCIENTIFIC AMERICAN SUPPLEMENT."

Copies have been filed in the libraries in different departments of the United States government. This catalogue is a valuable reference index to a whole scientific and technical literature, much of which has not yet been published in book form. We are still able to supply a limited number of cloth-bound copies, which are mailed for twenty-five cents. Copies of the paper cover edition mailed free to any address in the world.

Explosion of Acetylene Gas.

While experimenting with acetylene gas in his machine shop in Rochester, New York, on October 4, Valentine Long, his brother, Frank Long, and Jacob Fassott, an employe, were injured by an explosion of the tank used in making the experiment. Valentine Long's skull is fractured over his right eye and he lost the sight of both his eyes. It is said at the city hospital that he will probably die. The other two men are not seriously injured. The tank was a strange-looking affair, about two and a half feet in diameter and made of galvanized iron, with bands of iron running along the sides to give it strength. It was placed in Long's shop a few days ago by an acetylene company recently formed in Rochester, in which Mr. Long was interested. At the time of the accident Valentine Long was preparing to make a pattern for a new valve that is used on the tank. A lighted gas jet that stood about three feet above the tank is supposed to have ignited the acetylene and caused the explosion. Fassott had a narrow escape from instant death. A piece of the iron from the tank grazed his body, cutting off the buttons from his trousers and making a rent across the bosom of his shirt.

The Steamer Cymric Launched.

The new White Star Line steamer Cymric was launched at the yards of Harland & Wolff, Belfast, on October 12. The Cymric is a freight and passenger steamer of 12,000 tons and is considerably longer than the Georgic, which is the largest of the White Star freight steamers now in the New York service. It is stated that the White Star Line has contracted for over 100,000 tons of new steamer property. The Oceanic was to have been launched in January, 1898, but, owing to the strike in the engineering trade in Great Britain, it is possible it may not be launched until May or June.

A NOVEL HAND CAMERA.

The remarkable progress that has been made within the past few years in the construction of hand cameras, whereby their cheapness, lightness, compactness, simplicity and accuracy are some of the predominant points, is well exemplified in the camera called the Adlake, which is the subject of our illustrations.

The well known box form of camera is adopted, and comprises at the front all of the important essentials for good work; as, for example, a lens easily removable for cleaning, a set of diaphragms quickly adjusted, a very simple yet rapid shutter, easily released, positive in its movement and quickly adjustable for time or instantaneous exposures. There are also the usual two finders for taking the picture in a vertical or horizontal position. On the rear is a space for holding twelve remarkably compact and simply constructed metal plate holders, plainly observable in Fig. 1 and in detail in Fig. 2. Each plate is exposed separately, withdrawn from the box and transferred to the rear of the series until all, or as many as desired, are exposed, each holder having stamped on it a separate number.

The construction of the plate holder and mode of operation will be observed in Fig. 2. Two vertical grooves in the box on each side hold a metal plate holder frame having a small recess cut out in each side, as will be noticed by a black space in the upper part of Fig. 2. The thin metal plate holder, just thick enough to hold one glass plate, provided with a hinge side, the latter having on its upper edge and outer corners light wire clamping or locking springs, is pushed down in the metal plate holder frame just described. Just in front of the frame are two skeleton fingers, having at their upper ends curved portions which fit into the black recess shown in the plate holder frame, and are attached to the axis of a revolving shaft at the bottom, at the end of which is also a push crank projecting through the box, the knob being seen in Fig. 1, on the side. To make an exposure the finger frame is turned into a vertical position until it fits snugly into the plate holder frame. The plate holder is then inserted, which brings the corner projecting clamping wires into the curved ends of the finger frame. The cover of the box is shut, then the knob on the outside is pushed down. This carries forward the finger frame downward in the arc of a circle which takes with it the door of the plate holder, leaving the latter in a horizontal position on the bottom of the camera. After the exposure is made the knob is pushed up tightly, which closes the door of the holder, it being secured by the three wire clamping springs. The cover of the camera is opened, the plate holder removed and another plate inserted. The plate holder is made with a thin rabbet edge, in which the edge of the plate holder door, or side, fits and excludes all light.

Referring to the mechanism of the shutter, Fig. 3, it will be noticed that the shutter is of the ordinary oscillating fan-shaped type, having an elongated aperture, working on a pivot from one side to the other in opposite directions, and that a very small movement just below its axis produces rapid movement above. To this portion is attached a link secured to the lower end of a long swinging vertical arm, or lever, pivoted at the top, seen on the left. A rapid movement of this lever near its fulcrum will give an extremely rapid motion to the shutter. Behind this lever will be seen the pivoted black operating swinging lever, on the end of which is secured the operating oscillating spring, having one end attached to the long vertical lever not far from the fulcrum.

When the operating lever is pushed in one direction by the knob on the outside the spring is partly rotated until its center is above the attached end, causing the shutter lever to be suddenly pushed in the opposite direction, giving a corresponding rapid movement to the shutter. Pushing the operating lever in the opposite direction makes the spring carry the long lever to the other side. In this way a slight side pressure on the push button quickly operates the shutter without a jar or difficulty. A second pivoted lever (shown at the right, Fig. 3) pivoted at the bottom, to the axis of which is a flat spring, has a horizontal arm projecting from its center which engages with a like short arm projecting from the shutter proper. It may be called a time lever. When the button on the outside is pushed toward the lens, the arm on the lever engages the arm on the shutter and stops its movement, leaving the aperture open for time exposures. When pushed away from the lens, the lever releases the shutter and allows the latter to close.


Above the shutter and working just behind the lens will be observed a star-shaped diaphragm plate turning around its center and having three different apertures. On the surface of the plate are slight indents, which engage in the end of the horizontal flat locking

springs. The diaphragm plate is attached on the front to a rotating ring surrounding the finder lens, and is thus rotated from the outside to whatever working aperture is desired.

Convenient strap rings are attached to the handle of the camera for carrying it over the shoulder or on a bicycle. Pictures we have seen made with it are clear cut and distinct, showing that its cheapness is no bar to the production of good work.

Its simplicity and certainty of working are its salient features, while at the same time its strength of structure is such as to permit of rough handling without detriment.

The camera is manufactured by the Adams & West-




THE ADLAKE HAND CAMERA.

lake Company, 108 Ontario Street, Chicago, Ill., from whom further particulars may be had.

Kite Experiments at Night.

Mr. William A. Eddy recently tried some interesting experiments with kites at night. The first of these was a thermometer ascension. Three six foot kites were sent up bearing with them a self-registering thermometer which was to ascertain the temperature of the upper air. The thermometer's place on the kite string was indicated by a red lantern, and its altitude of 1,167 feet was calculated by triangulation on a base line of 525 feet. When the thermometer was sent aloft the temperature of the earth was 50 degrees. It was 48 degrees on the ground an hour later when the thermometer was hauled down, and the register showed that the minimum temperature of upper air was 46 degrees. The second ascension was made a few minutes later. The thermometer was raised to a height of 1,530 feet and left there ten minutes, and when it was drawn down it registered 47 degrees, while the ground tem-



THE PLATE HOLDER DEVICE.

THE SHUTTER.

perature was 44 degrees. The minimum temperature registered in the highest strata was 43 degrees. Mr. Eddy and his associates next raised a triangular reflector, 24 by 5 inches, covered with silver paper, to watch its operation in the light of a full moon and see what it would do with the rays. One of Mr. Eddy's associates went to a point a quarter of a mile distant, and from there could plainly see the reflector, although at first it was difficult to distinguish it from the stars.

A COMPANY has been organized at Seattle, Washington, to develop the coal and oil fields recently discovered in Alaska, some 350 miles west of Juneau. Thirty thousand feet of piping has been ordered for this purpose from the Pittsburgh district.

THE STEEL PIPE AND TUBE INDUSTRY.

I.—THE MANUFACTURE OF THE PIG IRON.


The manufacture of pipe and tubing is one of those branches of the iron industry that have been slow to discard puddled iron in favor of Bessemer steel as the raw material of manufacture. This reluctance to use the new material has been due to the difficulty in producing lap and butt welded steel pipe that would be as strong at the weld as in the body of the pipe, and it is undeniable that the earlier attempts were marked by repeated failure. The obvious advantages of strength and smaller cost in the use of steel were so great, however, as to stimulate the manufacturers to an earnest study of the problem, and of late years it has been so completely solved that welded steel pipe and tubing can now be made, and is made, that shows a larger percentage of strength at the weld than at any other point. It has been found that to procure a perfectly reliable weld a special grade of steel must be used, and that the chemical composition of the pig iron itself must be made the subject of careful study. Under the old system the manufacturers of steel tubing were apt to purchase their raw material in the shape of pig iron with very little, if any, regard to its composition; whereas it is now the practice of the best manufacturers to exercise the greatest care in the selection and mixture of the pig before it is melted down for treatment in the converters.

The National Tube Works Company, whose plant is the largest and most representative in the world, attach much importance to this branch of the manufacture, and they make every ton of pig that goes to their steel plant in their own blast furnaces. Every lot of pig that is cast is carefully analyzed and its composition recorded, and when the cupolas at the steel plant are charged the pig is selected from various casts with reference to its chemical composition, so that the molten cast iron as it is poured into the converters shall have the desired chemical proportions.


Before entering into a detailed description of the blast furnaces, it may be mentioned that the National Tube Works Company, whose plant has grown to such vast proportions, was formed in Boston in 1865, and is, therefore, thirty-two years old. It made a modest beginning at its present location, McKeesport, Pa., in 1872, with a pipe mill which employed two hundred men. The company at that time merely rolled the "skelp" (as the plates from which the pipe is made are called) into pipe, buying the skelp in the open market. In order to render themselves independent of the market and secure a more reliable material, they built in 1879 their own puddling furnaces and rolling mills. Shortly after this a forge was added, together with Swedish refineries and "knobbling" fires for the manufacture of the charcoal iron, of which the company's locomotive boiler tubes are made. The present steel plant was erected in 1893, and there is at present an entirely new plant in the course of erection for the manufacture of cold-drawn seamless tubing.

Thus has been built up the present vast establishment, which can claim to be not only the largest tube works in the world, but also one of the largest steel works of any kind in this country. Those of our readers who have never had an opportunity to visit a works of this magnitude can form some idea of its size from the following statistics: The combined steel plant and rolling mills cover an area of 90 acres and give steady employment to an army of 7,000 men. The raw material brought into the works and consumed every day averages 1,000 tons of ore, 1,500 tons of coal, 700 tons of coke and 300 tons of lime stone, not to mention other material in lesser quantities. For the intershipment of material within the works there are 12½ miles of standard gage track and one mile of narrow gage. The rolling stock of this system of railroads consists of 350 cars and 11 locomotives, the latter varying in size from the smallest of their kind up to machines of 75 tons weight. The total output of tubular goods for the year is 200,000 tons.


The raw material—coke, limestone and iron ore—is brought into the works on cars and run up onto raised trestles, from which it is dumped into long rows of bins. From these it is drawn off, as will be explained later, for charging the blast furnaces. The plant contains two blast furnaces, known as the Monongahela furnaces, of the latest type, with a capacity of about 700 tons per 24 hours. These furnaces, with the elevators for raising the ore, coke, etc., to the charging platform, the hot blast stoves and the foundry in which the pig iron is cast, are shown on the front page engraving. Each furnace consists of a massive cylindrical structure of brick and steel 80 feet in height and of varying diameter. At its mouth it has an internal diameter of 16 feet, and it increases in the first 60 feet of its depth to a diameter of 20 feet, the taper being



A 1450 HORSE POWER BLOWING ENGINE.




BATTERY OF THIRTY-SIX GAS-FIRED BOILERS.



THE BASE OF A FURNACE 80 FEET HIGH—CASTING THE METAL.



REMOVING PIG IRON FROM THE SAND.



LOADING ORE AT THE BINS FOR THE FURNACES.

MANUFACTURE OF STEEL TUBING—THE BLAST FURNACE PLANT.

given to allow of an easy descent of the material. The walls are 3 feet in thickness, and the greater part of their weight is carried upon a circular row of massive cast iron columns, which bear against heavy steel girders placed beneath an offset formed in the wall at this point. From here to the level of the blast tuyeres the furnace tapers to a diameter of 12 feet, and this diameter is maintained to the bottom of the furnace, 8 feet below the tuyeres. The massive walls are built of brick, with an outer casing of sheet iron and an inner lining of firebrick. It will thus be seen that a modern blast furnace presents the appearance of sections of two hollow truncated cones, placed base to base and terminating in a cylindrical chamber or basin. The upper portion is known as the "shaft" or "body," the lower portion as the "boshes," and below this is the "hearth" or "crucible," in which the molten cast iron collects. The boshes, it will be seen, lie just above the tuyeres, and as the material which they contain is exposed to the fierce blast of the furnace, the walls at this point are provided with hollow bronze castings built into the brickwork, through which a stream of cold water is constantly circulated. These extend completely around the boshes and penetrate the wall to within a few inches of its inner surface. At the bottom of the boshes the wall is pierced by seven tuyeres through which the hot blast is introduced.

In the earlier blast furnaces the hot gases were allowed to escape at the mouth of the furnace, from which great masses of flame issued continuously and gave that weird and brilliant night effect for which the iron manufacturing districts were formerly noted. This was, of course, an extremely wasteful practice, thousands of dollars' worth of fuel being recklessly burnt away to no purpose. To-day the mouth of every furnace is closed by a massive cast iron cup and cone arrangement, which is only opened when a fresh charge is to be lowered into the furnace. The cup is a massive casting, which rests upon the inner edge of the wall and extends down into the furnace mouth. The cone is suspended within the cup, its lower edge being of larger diameter than the cup, so that when it is drawn up it completely closes the opening.

On one side of the furnace, just below the hopper, is a flue opening, through which the gases escape down a larger riveted steel pipe to a dust collector, where the cinders and all solid particles remain and are taken out from time to time through a chute at the bottom. The gases are then utilized for two different purposes. Part of them is led to the Cowper hot blast stoves, where it heats the blast on its way from the blowers to the furnace, and part is conducted to the batteries of boilers, shown in Fig. 2, where it is utilized in raising steam for the blowing engines.


The Cowper stoves, of which there are seven, stand in a line opposite the furnaces. Each stove is a cylindrical wrought iron tower 20 feet in diameter and 79 feet 6 inches in height. It is closed by a dome-shaped roof, and the whole interior is lined with fire brick. On the side next the furnaces is a large vertical flue into which the furnace gases pass by a valve at the bottom. The body of the stove is taken up by a mass of fire brick pierced with innumerable small, vertical flues, extending from top to bottom and open at each end. The hot gases are ignited on entering the base of the large flue by admitting air through a valve, and the hot products pass up the main flue and down through the mass of fire brick, finally escaping to the large steel chimney, which stands between the furnaces. When the interior of the stove has been heated to a proper temperature, the gases are shut off and turned into the next stove. The cold blast from the blowers is now turned on at the bottom of the stove and passes up through the brickwork, from which it absorbs the heat, finally passing down the main flue, from which it is led to the circular blast main which surrounds the furnace just above the tuyeres. By the time it leaves the stoves the air is heated to from 1,300° to 1,400° Fahrenheit, the difference between this and the cold blast representing heat saved from the gases and restored to the furnaces.

The gases that are not used in the hot blast stoves are carried in large riveted pipes to the boiler house, of which we give an interior view, Fig. 2. Down each side of the room are arranged sixteen two-flue boilers, each of which is 54 inches diameter and 30 feet long. There are also four 250 horse power double deck water tube boilers in two batteries, making thirty-six boilers in all. All of these are fired with the furnace waste gas, which is distributed by the large pipes which extend through the boiler house near the roof. From the main pipe it is led down beneath the foot plates, and there controlled by valves which admit it to the burners, which will be noticed curving over from the floor to the furnace front. Here the air necessary for combustion is admitted, and the gases are burnt in the fire box. The supply of gas is controlled by means of a rack and lever, which serves to slide the burner to and from the furnace and increase or reduce the opening by which the gas enters it.

After passing down through the long line of boilers one is prepared to find an imposing display of motive machinery in the engine house—and it is indeed a truly

impressive sight that meets the eye. The blowing engines, one of which is shown in Fig. 1, are all gathered under one roof, and together they aggregate a total of nearly 5,000 horse power. On one side of the room is a group of five Allis-Corliss condensing blowing engines with 42 inch steam cylinders, 84 inch air cylinders, and a common stroke of 5 feet. Each engine develops 700 horse power, and each is provided with its own condensing pump. There is also a very handsome compound condensing blowing engine, of which we give an illustration, with a 40 inch high pressure and 76 inch low pressure cylinder, and two air cylinders 76 inches in diameter, the stroke being 5 feet. This engine develops 1,434 indicated horse power, and with the other engines brings the total up to close upon 5,000 horse power.

The 2,000 tons of limestone, coke and ore which are consumed daily by the furnaces are brought into the works by the train load. The cars are run up onto trestles, from which their contents are dumped into long rows of bins. Our illustration, Fig. 5, shows the chutes at the bottom of the ore bins, which latter are ranged down the long shed which is seen to the left in the front page engraving. The "burden," as the mixture of ore, limestone and coke with which the furnace is charged is called, is made up according to the grade of iron which it is desired to produce. It is taken from the bins in iron trucks in the proper portions, and wheeled to the large elevators shown in the engraving, which lift it in the trucks to the charging platform at the mouth of the furnace. Here it is dumped into the hopper, and as soon as the latter is filled, the cone is lowered, permitting the charge to fall into the furnace. The furnace is kept constantly filled with burden, and when it is once started it is kept burning continuously, the solids descending and the gases rising to be carried off by the flue. If we could look into and note the con-



TRANSVERSE SECTION THROUGH COWPER HOT BLAST STOVE.

dition of the contents, we should find at the top a layer several feet thick of raw materials, the temperature of which was about 500°. Below this would be a few feet in which the ore was somewhat reduced by carbon. In the next layer, at a temperature of 1,000°, the limestone would be found decomposed into lime and carbonic acid. Below this would be a wider belt at from 1,500 to 1,700 degrees temperature, where the iron, now reduced from the ore, would be taking up the carbon to form cast iron. A little lower down oxides, such as silica and phosphoric acid, are reduced, the silicon and phosphorus combining with the iron. Within the boshes the iron is completely melted, as is also the slag which results from the combination of the fluid with the various impurities. The molten mass finally collects in the hearth, the slag being on the top, and the heavier iron at the bottom. The slag is drawn off through an opening at the top of the hearth, and the cast iron is tapped through a narrow slit near the bottom. The illustration No. 3 is taken from the interior of the foundry in which the pigs are cast. In the foreground is seen the base of one of the great furnaces. The large circular pipe which surrounds it is the hot blast main, from which the seven smaller pipes lead to the tuyeres below. On one side is seen the trough through which the slag is drawn off, and on the other side the molten iron is being drawn off, through the tap hole. The cast takes place six times a day, and the total output of the two furnaces is about 700 tons per day. The sand is prepared by forming parallel lines of moulds which connect with the central channel down which the molten iron flows. The tap hole is opened by breaking away the clay with which it is closed, and the metal flows at a white heat down to the end of the main channel, where it spreads right and left into the moulds. The filling commences at the extreme end and finishes at the furnace.

When the cast has cooled off sufficiently to be handled, the pigs are broken loose and laid across each other in a position convenient for handling by the man who carries the heavy pair of tongs. (See Fig. 4.)

They are then lifted, one at a time, by a gang of powerful and well-muscled men, who carry them through the open archway at the side of the foundry and load them into cars on which they are hauled to the steel-making department.

We reserve the description of this department for a later issue.

M. de Morgan's Last Discovery in Egypt.

We may give a fuller account of discoveries which we mentioned briefly a few weeks since, says The Independent, made in the Nile Valley by M. de Morgan, Director-General of Antiquities of the Egyptian government. The most important of these discoveries is an extensive tomb which appears to be the most ancient yet unearthed in Egypt. M. de Morgan began his investigations in that portion of the Nile Valley formed by the bend in the Nile between Thebes and Abydos, where he brought to light many of the oldest records belonging to early Egyptian history that have yet been found.

The first notable discoveries were a number of ancient flint arrowheads, and other implements in the shape of indented flint blades, which had probably been used as saws and sickles. All of these evidently belonged to a period considerably antedating the time of the fourth dynasty. It is thought that the sickles date from even the first dynasty, for the reason that wheat is believed by historians to have grown wild in Egypt at that time, and that these implements were evidently used for harvesting this wild cereal. M. de Morgan also found evidences that these ancient people had a religion of their own, which he believes to have been a sort of fetichism, as he can in no other way explain the curious images, the slate figures of fishes, birds and turtles which he dug up. He says:

"These figurines must have belonged either to the first dynasty or to a race and period preceding it, as I have found them only in these autochthon places."

He adds that in no other tomb of the ancient empire that has been discovered have any fragments of this kind been found.

Continuing his study of the ground, M. de Morgan made his way along the valley until he reached a point near Negada, where an extraordinary mound attracted his attention. Excavations were begun at the base of the mound, and revealed the existence of a huge quadrangular-shaped tomb, which the explorers believed to be intact. One of the solid sides of the tomb was pierced, and an opening made the size of a large doorway. On entering the tomb it was found that various galleries extended at different angles, and long passageways with rows of carved columns descended into subterranean chambers. From top to bottom the walls were covered with hieroglyphic inscriptions and with figures of men and animals cut deeply into the surfaces. Warriors in bass-relief, different from anything seen in other tombs, and images of children, kneeling as if in fear, appeared here and there on the sides of the passageway.

The main gallery led into a series of twenty-one rooms, each containing many objects, such as pieces of furniture of different designs, fragments of bronze statues and a quantity of broken vases. In the center of each room were placed sarcophagi, containing the mummified remains of the dead. The vases were cut out of alabaster, rock crystal, quartz and a substance resembling obsidian, and were carved with peculiar designs. A large central room contained a single sarcophagus, resting upon a pedestal of solid rock. Around it, crudely carved in ivory, were forms of fishes and dogs; and near the feet were the remains of what appeared to be a mammoth lion, made of countless pieces of ivory put together. At the head of the sarcophagus and facing it was a life size statue of a man, carved in wood. The sides of the room were covered with inscriptions of a period so remote that interpretation was impossible. The explorers opened the sarcophagus, and found an inner mummy case, covered with hieroglyphics. The sarcophagus was then closed and sealed, and prepared for removal to the museum at Gizeh, where the body will be carefully unwrapped. The sarcophagi in the other rooms, all of which were supposed to contain the bodies of royal persons, were also removed to the museum, where they will be opened. In all the rooms, M. de Morgan found large urns tightly closed and having on top what is known as a "banner name," or the seal of the king—a conclusive proof of the great antiquity of the tomb. These, as well as all the fragments and other loose objects, were carried to the museum.

The ceilings of the passageways and rooms were lined with what appeared to be sun-dried bricks of coarse workmanship, while the pavements of the floors were of granite. In many places the walls were in such a crumbled condition that large portions of the inscriptions had become obliterated. The royal names upon the sarcophagi consisted of a few signs; and, instead of being written in cartouches, were inscribed in a square similar to the "banner name" on the vases. The seals on the vases in the king's chamber were made from a cylinder, and not from a scarab, according to the Egyptian fashion, as found in other royal tombs. Everything bore evidences of the most remote age.

Correspondence.

A Needed Patent Office Reform.

To the Editor of the SCIENTIFIC AMERICAN :

In your valued issue of the second instant you present an article on the "Proposed Amendments to Our Patent Laws."

In addition to the propositions of the National Association of Manufacturers of America, I desire to call your attention to an inconsistency in the present working of the Patent Office which forms a sufficient grievance for another amendment.

The injustice (and it is nothing less) to which I refer is the unnecessary time and delay consumed in getting an application for a patent through the Patent Office.

With a surplus of \$300,000 accumulated during the past year, and a total surplus to its credit of more than \$5,000,000, it would seem there is no excuse for submitting inventors to such long delays as is now the case in the examination of applications; especially, on the ground that the office is overworked, or that the force of examiners is insufficient to cope with the vast amount of business pouring into that office each day.

If more examiners are necessary to the proper dispatch of business, there is nothing to prevent the doubling or trebling of the present force, in the light of the resources at hand.

The writer has a number of applications for patents now before the Patent Office, and when he is told respecting one set of papers that this particular application "will come up for examination in about four months from the date of filing," it seems an absurd proposition for a government institution to make, which exists for and is backed and supported by an army of inventors, whose fees have enabled the office to pile up an unheard of surplus over and above its expenses.

Four months before one's application can reach an official examination! This is almost an insult to the inventive age, and certainly leads to the conclusion that there is large room for a grand reformation along this line, and that it is high time some action were taken looking to the correction of this evil and a betterment of this branch of our patent service.

In patent practice the great desideratum is the utmost dispatch consistent with absolute accuracy, and there is no reason why the United States Patent Office should not be so skillfully equipped as to be able to pass on each and every application in at least two weeks after the date of filing thereof.

To compel an inventor to wait four months or more, before he can know what the outcome of his application is to be, serves to tie his hands, and prevent him from marketing what might prove a valuable invention, and at the same time keeps out of his possession funds which are absolutely necessary to his work and welfare.

Were every inventor a manufacturer, then the time consumed in passing upon these applications would not so materially affect him, for he could manufacture his invention with the usual "Patent applied for" stamped thereon, and patiently wait the pleasure of the Patent Office; but when, as is now the case, inventors are dependent upon manufacturers, it is impossible to dispose of a patent which the Patent Office has not as yet granted; and as money is what the inventor needs, he is unjustly compelled to wait until the insufficient force of the Patent Office reaches and passes upon his application.

Unless some reform is inaugurated to correct this grievance, what is to be expected of the future, when the accumulation of applications at this date has put the examiners four months or more behind in their work? How does the office expect to cope with inventive expansion, if they find themselves handicapped with work at this stage? And why is that \$5,000,000 surplus lying idle, when it might be expended in supporting an increased force of examiners, and thus facilitate the work of examination?

If the National Association of Manufacturers of America are seeking amendments to the patent laws of this country, they would do well to incorporate the above in their repertoire, and thus bring about a badly needed reform.

WILLIAM E. HEATH.

Baltimore, October 9, 1897.

Electrical Show—Madison Square Garden Selected for the Second Exhibition.

Another electrical show has been planned for New York. Indications are it will be larger than the first, and for that reason the management lately signed a lease for Madison Square Garden for the month of May, 1898.

The exhibition company was incorporated in Albany last week. The officers are: C. O. Baker, Jr., president; F. W. Roebbling, vice president; George F. Porter, secretary and treasurer, who, with L. F. Requa, C. H. Lieb, H. H. Harrison and J. W. Godfrey, compose the board of directors. Mr. M. Nathan, the general superintendent of the last show, will have the management of this.

The new electrical inventions and improvements developed since the last show, and the interest and co-


operation of many manufacturers already assured, will count for much toward making this a more complete demonstration of all the applications of electricity and its branches than was possible in the first exhibition in 1896.

THE COLOR CHANGES IN LIZARDS.

BY C. F. HOLDER, PASADENA, CAL.

The chameleon of eastern countries has attained a world-wide reputation for its wonderful faculty of changing color. In America we have a lizard, shown in the accompanying illustration, which is, if not so remarkable, one of the most interesting of this group of animals. *Anolis principalis* is best and most familiarly known in Florida and some of the Southern States, where it darts about among the vines and other vegetation, mimicking the dark green verdure and presenting a really wonderful illustration of this singular phase of nature.

At one time I possessed several specimens of the anolis, and endeavored, with poor success, to introduce these little animals into Southern California, hoping that they would adapt themselves to the conditions which prevail here, but my lizards simply became pets and apparently preferred the house, where they were provided with flies and other delicacies. These little creatures were about five inches in length, of a general dark green hue shading to gray, assimilating the various objects upon which they rested slowly but



AMERICAN CHAMELEON (*ANOLIS PRINCIPALIS*).

very decidedly. I arranged several little corrals, one with a white base, another with a gray, another with a green, and changed the occupants about. In ten or fifteen minutes they very materially would adapt themselves to the new tint, though they never became white, the change then being merely a fading out of all lines, leaving the body a faint gray. At night they became a beautiful green, which may be considered their normal color. The changes made in confinement I am confident were not so rapid as those when the lizards were in their native Florida, where moisture and hot days and nights gave them the exact temperature necessary for their best display.

There is something mysterious and even uncanny in watching the change of color. When placed upon a green twig the little creature would immediately draw itself out, extend its front and hind legs at full length and become to all intents a part of the twig or branch, so that it was difficult to distinguish it. Meanwhile the mysterious blush of green was deepening and stealing over its back and sides, making the resemblance still more striking. The natural assumption of one who had given the subject no especial attention might be that the anolis had glanced around, and perceiving that it was presenting a contrast not favorable to its personal safety, had assumed a color more protective. In other words, that there was some intelligent act associated with the change. When the little creature was blindfolded it assumed the same tint as at night, and did not change when placed upon the most striking colors, showing that the eye was the involuntary

medium by which the different tints were obtained. The act of adaptation is perfectly involuntary, or made without the knowledge of the animal, being the effect which certain colors have upon the pigment cells of the animal. At least this is the generally accepted explanation, and the experiments which have been made with blind animals seem to show beyond question that the eye is the medium.

These peculiar changes, which are so well known in fishes and reptiles, can be understood by glancing at the pigment cells of a frog. The skin is seen to consist of two portions, the cutis and epidermis, the latter apparently being made up of cells. The cutis has large cavities among the nerves, which are commonly filled with pigment and are very sensitive, contracting and expanding in a remarkable way. The pigment cells are called chromatophores, and vary in color in different animals and in the parts of each animal, and may be red, brown, green, yellow, black or various shades. The color of the chromatophores appears to change during contraction or expansion and constitutes a most complicated and delicate study. Thus, in a little fish (*Gobius Ruthensparri*), Heineke, the German naturalist, while watching its yellow pigment cells, saw them gradually expand and become black.

These cells are distributed all over the body with more or less regularity, and upon their contraction and expansion depends the prevailing color of the animal. Thus, if the pigment cells or chromatophores expand, the prevailing color will become black and the very light spots in the animal dull. On the other hand, if they contract, a reverse effect obtains. Exactly how these wonderful changes in all animals which adapt themselves to their environment are produced is not known, but it is assumed that certain colors through the medium of the optic nerve produce contraction or expansion, and the result is a protective tint or one which assimilates that upon which the animal is resting. The eye receives the stimulus or impression, which passes from the optic nerve to the sympathetic nerve, so reaching the various series of chromatophores. Thus, when a flounder is taken from the sandy bottom and placed on a black bottom, it at once grows darker; in other words, the color of the bottom has in the manner described caused a relaxation of the chromatophores, and the brown and orange colored ones have turned black or dark, thus aiding in the protection of the animal—a protection at once remarkable and interesting. Among the flounders this is very marked. In the octopus I have produced almost instant changes, waves of color being seen to pass over the animal. This is especially noticeable in the little squid cranchia, while the larger squids are marvelous illustrations of this faculty. The dolphin, so common in the Atlantic, is well known for its wonderful changes, not necessarily protective.

The little Florida anolis is easily domesticated, and two specimens kept by me became interesting pets, crawling about without the slightest fear; seeking the snug shelter of the binding of a book in cool weather, coming out to bask in the hot sunshine, showing themselves to be perfect thermometers.

It is doubtful if the anolis would thrive in Southern California as the nights are often very cool. All through the winter here all the reptiles enter what is known as a winter sleep or partial hibernation. At half past four, or as soon as the direct rays of the sun begin to be missed, the lizards leave the rock heaps where they have been sunning themselves, and crawl into the crevices and into holes in the ground, stretch out their limbs to the rear, stiffen, and enter what is apparently complete hibernation; but, as the sun rises the following day, they are warmed into life again and renew all their activity.

Automatic Coupler Law.

The Chicago and Alton Railroad and other roads recently filed petitions with the Interstate Commerce Commission asking for extension of time within which their cars, under the act of March 2, 1893, are required to be equipped with the automatic couplers and power or train brakes, the time fixed by the act being January 1, 1898. The commission has made an order fixing the hearing of such petitions for Wednesday, December 1.

The commission has also ordered that any railroad filing application for extension shall also make, on or before November 20, 1897, a statement under oath of the number of freight cars owned and the number of freight cars which will be equipped with automatic couplers and the number which will be equipped with power or train brakes by December 1, 1897, and the number of freight cars which have been equipped with automatic couplers and the number which have been equipped with power or train brakes each calendar year since the act went into effect.

Airship Crosses to France.

Cablegrams from France state that the balloon of Charles Pollock, who started from Eastbourne, England, October 12, across the Channel, descended safely near Domart, fourteen miles northwest of Amiens.

The Effect of Great Cold on Animalcules, Worms, Insects and Other Animals.

BY JAMES WEIR, JR., M.D.

That certain animalcules, worms, insects and other animals can and do experience no appreciable harm when subjected to extremely low degrees of temperature, the following experiments and observations would, unquestionably, indicate.

Until, comparatively speaking, a few years ago, freezing was considered to be absolutely fatal to all forms of animal and vegetable life. So universal was this belief that contaminated and filthy water was thought, by both scientist and layman, to be rendered potable after it had been subjected to great cold. Some ten or fifteen years ago, however, several severe epidemics of typhoid fever were traced directly to the use of ice which had been taken from ponds into which there flowed surface drainage. This observation occasioned an entirely new opinion to be formed.

In 1889, I subjected various cultivations of the specific germs of tuberculosis, typhoid fever, cholera and anthrax, by artificial means, to degrees of temperature far below any degree of cold that ever occurs naturally. These colonies were in bouillon, agar agar, and other culture media and were, therefore, easily studied. When the media containing germ colonies were gradually thawed out and then submitted to microscopic examination, no appreciable change in the various microbes was to be observed. When minute portions of these colonies were transferred to fresh culture media, the germs immediately began to increase and multiply, thus showing that they had not been killed or even injured by the intense cold to which they had been subjected. It is claimed that the germs of yellow fever and kindred diseases are destroyed by cold. If this is true (and I have no reason to think that it is not), this fact goes far toward demonstrating the truthfulness of a proposition which I have long advocated, namely, that there are two kinds of microbes—the animal and the vegetable. It has long been known that intense cold is fatal to many organisms known to be vegetable, while, on the other hand, none of the microscopic animalcules are killed by the process of freezing alone.

Infusorians appear to be uninjured by great cold, even when it lasts for weeks at a time. An experiment, and one easily performed, will demonstrate to any one the truthfulness of this assertion.

Let the observer satisfy himself that the pond or ditch from which he wishes to take the ice necessary for this experiment contains the infusorian, say the "slipper animalcule" (*Paramecium*); this he can do in October or November. Then, in the depths of winter, when the ice is thick on the ditch, after a hard and long-continued freeze, let him take a small piece of the ice (a portion containing confervoid growths will be necessary, as this particular infusorian seeks shelter thereon), gradually thaw it out, and then place a drop of the water or a bit of conferva beneath the object glass of his microscope. He will soon discover *paramecia* full of life, and absolutely unaffected by their sojourn in their ice envelope.

Vorticellæ or "bell animalcules," so called from their bell-like shape, draw in their cilia and shrink upon or coil their stalks just before the water becomes congealed. This interesting performance can easily be observed if a colony of these animalcules is watched on the stage of a microscope. This observation, to be successful, must be carried out in a room whose temperature is about 18° F. A fragment of duckweed, alga, or any pond weed known to be inhabited by vorticellæ should be placed in a drop of water beneath the object glass. The stage and glass slide will rapidly become cold. Finally, the drop of water will freeze, but, just before congelation takes place, the vorticellæ will draw in their cilia, coil their stalks and sink to rest on the weed. If the slide be carried into a warm room and the drop gradually melted, the little creatures will soon begin to erect themselves on their stalks and to move their cilia in the act of feeding. A certain rhythmical pulsing of the umbrella (nectocalyx) of a medusa or jelly fish can be noticed as the creature swims in the water. This pulsing varies in frequency according to circumstances. When medusæ are placed in water whose temperature is being gradually lowered, at first this rhythmical motion will be accelerated. I have seen the nectocalyx under such circumstances pulsate so rapidly that its movements could hardly be counted. Gradually, however, as the water neared the freezing point, this pulsing would become slower and slower and finally cease. This inactivity would disappear, however, as soon as the temperature of the water became higher. Semper asserts that long-continued freezing is fatal to all infusory animalcules. Now this statement is misleading and indefinite, from the fact that he does not fix a time limit. I am certain that several days' freezing is not fatal to the infusorians which I had under observation. I have also found live infusorians in the sediment of ice water, the ice from which it was derived having been harvested several months previous to the time of examination. These forms were not adventitious, but were true fresh water infusorians (*Paramecium*). The contractile vesicle (the infusory heart)

of this little animal gradually slows its "pulse" as the temperature is lowered, and finally ceases all motion. Yet the creature is not dead, for, if judiciously thawed out, it will resume all of its functions. Rhizopods, rotifers and other animalcules likewise stand freezing with perfect impunity. In fact, all cold-blooded water animals appear to be indifferent to the lethal effects of extreme cold.

Last winter, while carrying on these investigations, I observed a very curious thing. I was examining a giant water beetle which was frozen in a lump of ice. I noticed, just below the head of this insect, an uncongealed drop of water; in this clear drop, not unlike kindred drops sometimes found in quartz crystals, I observed a little animal swimming freely about. I could not make out its genus through the intervening ice; so fractured the lump in order to obtain the animalcule. Unfortunately, it was lost and I cannot describe it. Had this creature an inherent quality which kept the water in its immediate vicinity in a fluid state, thus affording it safe domicile during winter, or was the drop due to some law of crystallization? The little mite seemed to be perfectly at home, no matter what gave rise to its miniature lake.

Some of the higher water animals, such as fishes and frogs, can endure great cold without harm. Not long since, I saw a carp (*C. carpio*) in the very center of a cube of ice. This fish resumed all the functions of life as soon as the ice melted and set it free. It is claimed by explorers that the waters of the North Polar seas are remarkably destitute of the lowest forms of life; indeed, of all forms. Yet that they are absolutely without life has not been shown, for even in the ice cold waters of the extreme North Arctic Ocean microscopic animalcules, to a limited extent, defy the benumbing and otherwise fatal touch of the Frost King!

Turbellarians, nematoids or thread worms undergo freezing without appreciable harm. Little worms will frequently be found in ice taken from ponds, lakes, etc. This has given rise to the idea that ice "breeds worms." These little creatures are simply nematoids which have become frozen in the ice and which have been liberated by liquefaction.

The common earth worm (*L. terrestris*) may be frozen stiff without experiencing any harm whatever. Several earth worms were taken by me from a vermicularium and placed in a jar containing earth. This was done early in autumn, so that the creatures might become accustomed to their surroundings by the time winter set in. Every now and then decaying vegetable substances, such as leaves, rotten wood, etc., were sprinkled over the surface of the earth in the jar; water was also occasionally sprayed in. Thus, the worms had an abundance of food and water. The jar was set out in the open air, though a roof of boards was placed above it to keep off the snow and rain. It was subjected to all the cold of a severe winter. On one occasion the thermometer registered -10° F. in the center of the jar for ten or twelve hours. As soon as the milder weather of spring set in, the worms began to move about, some of them laying eggs, thus showing that they had not been hurt by a temperature many degrees below freezing point. Again, several worms were taken from a vermicularium and surrounded by an envelope of dampened earth an inch in thickness; they were then exposed to a temperature of -10° F. for ten hours. When examined, they were found to be almost rigid; indeed, some were quite so, breaking in the fingers when they were bent. Yet these worms (that is, the unbroken ones), when gradually thawed out, showed no sign of injury.

Last autumn I saw a bumblebee take up her winter quarters beneath the bark of a locust tree. The fragment of bark under which she crept was slightly resilient, so that she was partly supported in her place by its elasticity. She was fully exposed on all sides, save her shoulders and part of her back, to the air; the piece of bark made a very efficient roof which kept off the snow and rain. During a cold wave, when the thermometer registered -6° F., I lifted the bark and removed the insect with forceps. I would not touch her with my fingers. I was afraid that their warmth might produce local temperature changes on her body, thereby inciting frost bite. She was, to all appearances, frozen through and through. Here was this insect (covered only with her own velvet robe), surrounded by an atmosphere whose temperature was a half dozen degrees below zero. The very tree on which she rested was being riven and split asunder by the intense cold. Was she alive, or did I hold in my forceps only a frozen, inanimate lump of gauzy wings, legs, body, intestines, etc.? This question was answered later on; in fact, on the fourth day of April, when she awoke from her long winter sleep and resumed her place in the economy of animated nature. I happened to be near when she awoke and came out on the bark. She carefully smoothed down her velvety body covering of black and yellow and essayed a short flight. She then flew to a pot of water and drank a long, deep draught. Finally, she flew about the lawn as if in search of something. And so she was. She was looking for a suitable spot in which to establish a

nest. This she eventually selected near a rose bush and soon disappeared beneath the turf.

The common toad (*B. lentiginosus*), at the approach of winter, burrows an inch or two into the ground and, surrounded by the roots of grasses, weeds, or herbs, goes into its winter sleep. Last November I saw one take shelter beneath a tussock of couch grass (*T. repens*), boring its way beneath and between the tough roots by a rooting motion of its head. Its fore legs or "arms" and its fingerlike claws were also used to great advantage, as well as its muscular hind legs in excavating and shaping its winter "dugout." At one time during the winter the soil was frozen solid to the depth of four inches. During this cold spell, I carefully dug up the tussock of grass and, upon examination, found the toad stiff and, seemingly, frozen through and through. I replaced both grass and toad, packing the frozen earth about the roots as well as I could under the circumstances. On the 18th of March I again dug up the toad. It was, to a certain extent, torpid, but, otherwise, was entirely uninjured by the great cold through which it had passed.

A friend, on one occasion, was blasting out stumps on his plantation, when a large mass or ball of snakes of various kinds was unearthed and exposed to view, all of which, seemingly, were without life. It was very cold, in fact, some 8° or 10° below zero. This gentleman placed a thermometer in the center of the ball of snakes and found that it registered 5° below zero. He carried home a large black snake (*Bascanion constrictor*) and a small copperhead (*Ancistrodon contortrix*). The snakes were gradually warmed and soon gave such unmistakable evidence of returning animation that they were summarily dealt with. Now, an interesting question intervenes. These two species are, generally, very bitter enemies. Do they lay aside personal animosity at the approach of winter and seek one another for mutual protection, or do their natures change at or about the time of the inception of hibernation?

We have seen that animals may be frozen through and through and yet suffer no harm. Where, then, dwells the vital principle in these creatures—in what organ or organs? Reduced to a frozen mass, they yet hold within themselves the elements of life which only need the awakening touch of heat to be set in operation. Of what character is that mainspring, which, although, for the time being, completely locked as it is in the hard grasp of the Ice King, is, nevertheless, through the influence of warmth, set free, and at once resumes its power and puts in motion the phenomena of life?

When we come to examine the higher animals, we find that some of them are able to endure very great cold. In fact, it has been demonstrated that the internal temperature of some of these animals, during winter, approximates that of the external atmosphere. In the case of the zisel (*Spermophilus citellus*) Horvath declares that he detected a temperature of 2° C. Says Semper: "The zisel, when lying in its winter sleep, always has the same, or nearly the same, degree of warmth as the surrounding air. In one case the temperature was 2° above zero, and a thermometer showed that its internal temperature was exactly the same; in another experiment the animal was sleeping in a room, at about 9° to 10°, for several days, and its internal temperature was 8.4°." Thus it will be seen that in this animal we have the wonderful phenomenon of a warm-blooded creature changing to a cold-blooded creature in winter, "since its temperature corresponds with that of the surrounding atmosphere." Most of the warm-blooded hibernating animals, however, keep up their internal heat by the oxidation of their fat; thus, the bear, the opossum and the raccoon, which on entering the winter sleep are remarkably fat, but which, when they awake in the spring, are thin and lean. Some rodents, however, show comparatively speaking very low temperatures; for instance, the ground hog, in which, on several occasions, I have detected a temperature as low as 60° F.

A Trolley Ride One Hundred and Twenty-four Miles Long.

The network of trolleys with which New England is now covered makes it possible for any one to ride for 124 miles on trolley roads. This is probably the longest trolley line in the world. Of course the trip would have to be made in a number of cars. From the residence of Mr. Henry H. Rogers, vice president of the Standard Oil Company, at Fort Phoenix, in Fairhaven, to Nashua, New Hampshire, the route is as follows: New Bedford, Fall River, Taunton, Bridgewater, Brockton, Braintree, Quincy, Boston, Malden, Melrose, Wakefield, Reading, Wilmington, Billerica, Lowell and Dracut, to Nashua.

PENMARCH lighthouse, on the Brittany coast, with its 10,000,000 candle power electric light, 180 feet above sea level and visible sixty miles away, is a monument to Marshal Davoust, Duke of Auerstadt, his daughter having given the French government \$60,000 for the purpose.

RECENTLY PATENTED INVENTIONS.

Engineering.

POWER DEVICE FOR PUMPING WELLS.

—Joseph J. Kwis, Findlay, Ohio. According to the novel construction provided by this invention, a practically direct connection can be made between the engine or other motor used and the mechanism employed for operating the surface rods in oil pumping machinery, the motion being so communicated through the driving wheel as to prevent any twisting strain whatever on the shafts. The device is compact, durable and inexpensive, and may, if necessary, be secured to a single timber, dispensing with a built-up foundation.

Mechanical.

PIPE WRENCH.—Edward B. Charlet,

Kewanee, Ill. The stock of this wrench has a slightly curved, toothed forward end, and in an opening in the rear of the curved toothed portion is pivoted a hook-shaped jaw, having teeth to operate in conjunction with teeth on the stock. In a notch in the stock is held the rear end of a spring whose forward end bears against the back of the hook-shaped jaw, to throw it into engagement with a pipe or other article to be gripped, a sleeve holding the spring in position, and the tension of the spring being increased by slipping the sleeve forward.

Agricultural.

CULTIVATOR.—George McDougall, Cedar

Junction, Kansas. For the cultivation especially of listed corn, this cultivator is made with parallel runners connected by arches, above which is the driver's seat, the rear end of each runner being inclined inwardly and carrying upon a spindle a cultivator disk. By means of levers which extend up within convenient reach of the driver the cultivator disks may be brought to any desired angle to the row of corn under cultivation, and locked in such position, causing the dirt to be heaped up to a greater or less extent around the roots. Arms extend outwardly from the runners to smooth the ridges between rows.

DISK PULVERIZER.—David Harper, Scott County (Post Office, Neelyville, Morgan County), Ill. Upon a pair of axles supporting a main frame, according to this invention, is mounted a front and a rear series of rotating disks or pulverizers, the series on each axle being adapted to be moved to an adjusted position in unison, and the series on one axle being held for movement independently of the series on the opposing axle, by means of operating levers which extend up through the platform in convenient reach of the driver. All of the disks on the rear shaft may, if desired, be set crosswise to the right or left, and held to such position by pawl and rack devices on the lever, the cultivator being designed to leave the ground in proper condition for the harrow after the first cut.

Miscellaneous.

MECHANICAL CALCULATOR.

—Robert Duncan, Knoxville, Tenn. This is a device more especially designed to facilitate computing the charge to be made for a guest at a hotel, without mental figuring, and it may also be used for ascertaining amounts due workmen, or, with slight changes, for computing interest, etc. It comprises a casing in which are mounted a calendar and cost price disk and a rotary rate disk. Four separate divisions of the day are noted for computing the cost from the time of entry to the departure of a guest, the clerk then simply moving the disks to correspond thereto, and finding in a properly marked division the total sum due, indicating the amount of the bill.

TALLY SHEET.—Herbert L. Baker, White Castle, La. For books having tally sheets used by lumbermen this invention provides an improved sheet arranged to permit of readily writing the tally marks in the proper spaces, and to indicate at a glance the total number of feet in any number of pieces of lumber. The sheet has a head line of figures to show the number of pieces tallied on each line, a column of figures to show the amount of each piece tallied, and spaces for receiving the tally marks, whereby the lumberman can conveniently keep tally on the sheet at the proper place and at the same time instantly read the total amount in feet.

SECTION LINER FOR PARALLEL

RULERS.—John C. Richardson, Middlesborough, Ky. An attachment enabling the user of a parallel ruler to conveniently and rapidly draw with the ruler sectional lines equally spaced apart forms the subject of a patent issued to this inventor. An arm slidably and adjustably held on one member of the ruler has its other end projecting over the other member, the projecting end being provided with a foot adapted to engage a stop pin on the member over which the free end of the arm projects.

MUSICAL INSTRUMENT.

—Benjamin McLaughlin, Boston, Mass. This invention is for an improvement in instruments of the banjo, guitar, mandolin and violin type, whereby may be obtained a tone of greater volume and purer quality, while also affording convenient means for raising and lowering the pitch of the instrument after the strings have been tuned. It consists principally in the employment of a resonator, located in the body of the instrument, its upper surface being adapted to engage the bridge, and it being engaged by an adjusting screw, whereby the resonator may be moved to and from the bridge to increase or decrease the resonant qualities of the instrument, and raise or lower or change the key or pitch, without necessitating the manipulation of the keys. The invention also provides a novel arrangement of the bridge.

FRAMING FOR FURNITURE.

—John C. Horn, Chicago, Ill. In the construction of such articles as desks, bureaux, chiffoniers, etc., this invention provides for their framing by means of corner posts having dovetail slots, longitudinal bars and locking bars having tenons on their ends, etc., in such manner that the

furniture may be put together without using glued joints for holding the parts, and so that it may be shipped in knock-down form without liability to marring the finish, and readily put together without any special skill. The construction is such that all the work of preparing the parts may be done by machinery, thus making such furniture comparatively inexpensive, while it is of less weight than ordinary furniture.

KNIFE GUARD.—Frank W. Waite and

William D. Broadwell, Petersburg, Va. This is a device adapted to be applied on the cutting edge of a knife and held there by spring tongues, to limit the depth of cut, thus adapting a portion of the blade to the especial purpose of removing the rind or skin from fruits or vegetables and absolutely preventing this portion of the blade from cutting into the article being prepared, although leaving the greater portion of the blade available for slicing, cutting, etc. The device is simple and inexpensive and readily applied or removed from the blade.

CURRYCOMB AND BRUSH.—Martin V.

B. Gr. Fey, Moscow, Ky. This is a combination implement adapted to be used separately or together, the brush being hinged to the comb and adapted to be folded back thereon with its back toward the back of the comb, or to be turned down to have the same face with the comb, there being means for fastening the brush in either of these positions. It is evident that when the comb and brush are fastened in line with one another the horse is both combed and brushed by each single stroke. Springs connect the currycomb with the handle frame, and its teeth thus become somewhat yielding, as are the bristles of the brush.

CARRIAGE CALL.—John A. Kunkel,

New York City. The noise and confusion usually attendant upon the calling of carriages when theaters are out or the opera is over, or after a numerously attended reception, often amount to a very serious annoyance, and to obviate this difficulty is the object of this invention. In a casing with guideways are placed multiple series of transparent plates, each carrying a numeral, and means are provided whereby, on simply pulling a cord, the attendant may elevate any desired numeral designation so that it may be seen by everyone in the vicinity, the range of the device covering any designation from 1 to 999, and thus taking in the number of any carriage it may be desired to call.

BALE BAND TIGHTENER.—John L.

Duval, Houston, Texas. To permit the operator to conveniently place the bands in position and fasten the ends together after the bale is pressed, this invention provides for the use of platens, each having grooves or recesses for the bands, while spring-pressed bars extend between the grooves or recesses and beyond the face of the platen, serving as guides for the bands and a support for the bale before it is compressed, the bars receding into recesses in the platen when pressure is brought to bear on the latter.

NON-REFILLABLE BOTTLE.

Louis J. A. Fernandes, New York City. This bottle is made entirely of glass, and has a valve, so arranged that the contents of the bottle may be poured out, but the bottle cannot be again refilled for use as an original package. Within the neck is a valve cage, and an upper extension of the neck, in which the cork is placed, is fitted on and held in position by a suitable cement, after the bottle is filled. A spring presses the valve to closed position when the bottle is held upright or in horizontal position, but, when the bottle is tipped farther over, the spring yields to allow the valve to open and the liquid to flow out.

DISTILLING APPARATUS.—Jose Galle-

gos, Antigua, Guatemala. This invention provides means whereby the pressure within the apparatus will be kept practically constant, by connection with an expansion chamber whose capacity is regulated by a counterweight, thus preventing any excessive pressure that might burst the apparatus. Any loss of vapors of the substance under distillation is also most effectively provided against.

NOTE.—Copies of any of the above patents will be furnished by Munn & Co. for 10 cents each. Please send name of the patentee, title of invention, and date of this paper.

NEW BOOKS, ETC.

ELECTRIC SMELTING AND REFINING.

By Dr. W. Borchers and Walter G. McMillan. Philadelphia: J. B. Lipincott Company. Pp. 415. Price \$6 50.

The "Elektro-Metallurgie" of Dr. Borchers has been for quite a period a leading authority upon the subject with German engineers, and this volume is a new edition of this work, translated and with additions by Mr. McMillan, lecturer on metallurgy in Mason College, Birmingham. The author has had twelve years' practical work in chemical and metallurgical industries, and treats of all those metals in whose extraction and working the electric current has found any application, excluding, however, electrolytic analysis and electroplating. To each chapter is also added a short survey of the purely metallurgical methods of treating the metals, so that the reader may compare such processes with the electrometallurgical processes. All of the descriptions are brought down to include the most recent developments in the art, enough being stated under each of the various metals, separately, to give a good general idea of the present industrial position of that branch of the subject.

MODES OF MOTION; OR, MECHANICAL

CONCEPTIONS OF PHYSICAL PHENOMENA. By A. E. Dolbear. Boston. Pp. 119. Price 75 cents.

The professor of physics at Tufts College endeavors, in this little volume, to make it clear how one kind of energy is converted into another kind, and the conditions needed for transforming it. Electrical and magnetic phenomena are presented as depending upon simple mechanical conditions, and a chapter is given to luminous ether.

Business and Personal.

The charge for insertion under this head is One Dollar a line for each insertion; about eight words to a line. Advertisements must be received at publication office as early as Thursday morning to appear in the following week's issue.

Marine Iron Works. Chicago. Catalogue free.
For logging engines. J. S. Mundy, Newark, N. J.
"U. S." Metal Polish. Indianapolis. Samples free.
Yankee Notions. Waterbury Button Co., Waterbury, Ct.
Handle & Spoke Mch. Ober Lathe Co., Chagrin Falls, O.
Walling Excavations. Patent for sale, United States or Canada. W. C. Thomas, Kansas City, Mo.
We make small metal goods and novelties for other people. Place & Terry, 247 Centre Street, New York.
Improved Bicycle Machinery of every description. The Garvin Machine Co., Spring and Varick Sts., N. Y.
Concrete Houses—cheaper than brick, superior to stone. "Ransome," 757 Monadnock Block, Chicago.
For static machines for all purposes, and X ray apparatus, write Reedsburg Electric Mfg. Co., Reedsburg, Wis., U. S. A.
Machinery manufacturers, attention! Concrete and mortar mixing mills. Exclusive rights for sale. "Ransome," 757 Monadnock Block, Chicago.
The celebrated "Hornsbly-Akroyd" Patent Safety Oil Engine is built by the De La Vergne Refrigerating Machine Company. Foot of East 138th Street, New York.
The best book for electricians and beginners in electricity is "Experimental Science," by Geo. M. Hopkins. By mail, \$4. Munn & Co., publishers, 361 Broadway, N. Y.
Send for new and complete catalogue of Scientific and other Books for sale by Munn & Co., 361 Broadway, New York. Free on application.

Notes & Queries

HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication.
References to former articles or answers should give date of paper and page or number of question.
Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and though we endeavor to reply to all either by letter or in this department, each must take his turn.
Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same.
Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.
Scientific American Supplements referred to may be had at the office. Price 10 cents each.
Books referred to promptly supplied on receipt of price.
Minerals sent for examination should be distinctly marked or labeled.

(7221) W. A. P. asks: 1. What is water

hammer and its causes? A. Water hammer in pipes is caused by the surging of the water in partially filled steam or water pipes. In steam or return pipes in heating apparatus air or steam may be lodged in places along horizontal pipes, separating portions of water, which, by the natural condition of moving water, produces wave motion and impact upon the inner surface of the pipe. In water pipes the presence of air in horizontal pipes produces the same action as in heating pipes. The absence of air in the water pipes of a house near the bibbs causes water ram by the sudden closing of a bibb, due to the arrest of the momentum in the long column of water in motion. The air chambers in plumbing work act as a cushion. 2. How can the true water level in a boiler be told when it is foaming, and what is the best thing to do when you find that the boiler is foaming? A. The water level may be judged from the mean of the water surge in the water gage. If gage cocks only are used, the approximate water level may be judged from the manner of opening the gage cocks. By slightly opening the gage cocks one after the other, you may obtain clear steam from the upper gage, a drizzle of water and steam from the middle gage and more solid water from the lower gage, when the mean height is between the middle and lower gage, with variations suitable to high or low water. A boiler may foam from excessive use of steam or from foul water, want of cleaning, etc. An engineer should always be able to judge whether the boiler is too small for its work or whether dirty water and want of cleaning is the cause of foaming.

INDEX OF INVENTIONS

For which Letters Patent of the United States were Granted

OCTOBER 12, 1897,

AND EACH BEARING THAT DATE.

[See note at end of list about copies of these patents.]

Acids and making same, compound of gamma-oxypiperidin-carbo. G. Merling..... 591,483
Adjustable wrench, E. P. Drew..... 591,743
Air compressing engine, Barbour & Hansen..... 591,584
Air cooling apparatus, T. B. Lightfoot..... 591,655
Air ship, D. Reed..... 591,692
Alarm. See Fire alarm.
Alarm circuit, protecting, I. E. Barriecrow..... 591,725
Alloy, metallic, C. F. Hitchcock..... 591,604
Amalgamating and extracting gold, etc., from dry crushed ore, apparatus for, E. L. Oppermann..... 591,682
Amalgamator, W. L. Brown..... 591,587
Animal trap, J. A. Allen..... 591,719
Animal trap, J. J. Drew..... 591,744
Atomizer, N. Du Brul..... 591,745
Axiomatic, W. B. Behnke..... 591,729
Axle for wheeled vehicles, trussed, J. S. Brown..... 591,736
Bag filler, R. O. Campbell..... 591,381
Bale tie machine, O. K. Harry..... 591,532
Barrel lining, C. E. Cottrell..... 591,455
Battery. See Galvanic battery.
Bearing, ball, W. H. Mackutchan..... 591,482
Bearing for shafts, end, P. A. Schumacher..... 591,502
Bed, spring, J. A. Gakeler..... 591,464
Bed, spring, W. C. Van Cise..... 591,579
Bell, bicycle, S. Goulden..... 591,589
Belt hook, J. B. Norton..... 591,681

Belt or band for driving machinery, Wetherill & Armitage..... 591,711
Belts, device for preventing slipping of, F. Scheben..... 591,600
Bench dog, E. Zimmerman..... 591,619
Bench dog, adjustable, H. H. Brocksmith..... 591,618
Bicycle, F. D. Maltby..... 591,673
Bicycle, L. F. Parks..... 591,566
Bicycle attachment, H. J. Richter..... 591,636
Bicycle flower holder, J. F. Dunnigan..... 591,330
Bicycle gearing, S. McMullin..... 591,488
Bicycle saddle frame and holder, B. S. Seaman..... 591,573
Bicycle support, J. Harper..... 591,602
Billets or ingots, apparatus for making hollow, J. Stevenson, Jr..... 591,433
Billard cue tip, G. Muller..... 591,487
Binder, temporary, J. L. & W. J. Rile..... 591,538
Binnacle, F. M. Wherren..... 591,442
Blast generator, automatic, A. M. Sidwell, Jr..... 591,659
Boiler. See Steam boiler.
Book support, E. F. Jewell..... 591,705
Boot or shoe, F. E. Phraim..... 591,646
Bottle, A. Few..... 591,688
Bottle, non-refillable, G. F. Barrett..... 591,724
Bottle, non-refillable, Hampshire & Davison..... 591,400
Bottle, non-refillable, Hodgson & Rickards..... 591,763
Bottle or similar vessel, G. M. Broemler..... 591,619
Bottle stopper and holder for same, W. Haskins..... 591,402
Bottle stopper attachment for bottles, jugs, jars, etc., G. F. Johnson..... 591,668
Bottles or drinking glasses, mouth guard and protector for, Donahue & Leach..... 591,778
Box. See Match box. Stamp box.
Box or receptacle for pulverulent or granular materials, R. Walsh..... 591,708
Bracket. See Roof bracket.
Brake. See Car brake. Fluid pressure brake.
Brake release mechanism, automatic hand, T. Eubank..... 591,666
Brake release mechanism, hand, T. Eubank..... 591,667
Brick, H. Penley..... 591,783
Bridle, H. Mayes..... 591,631
Brush, fountain, J. W. Poor..... 591,570
Burner. See Hydrocarbon burner. Incandescent burner.
Button, F. G. Neubert..... 591,564
Cabinet, G. C. Smith..... 591,574
Cabinet, form, Crandall & Byrnes..... 591,739
Caisson, air lock, J. F. O'Rourke..... 591,633
Caisson shaft, J. F. O'Rourke..... 591,632
Can opener, wire cutter and corkscrew, attached, A. Dell..... 591,459
Canceling machine, card, A. A. Low..... 591,630
Candelabrum, J. Markowsky..... 591,557
Cane and camp stool, combined, J. H. A. Behrens..... 591,549
Car brake, W. Timmis..... 591,577
Car coupling, L. Collis..... 591,385
Car, dumping, O. C. Bauer..... 591,585
Car dumping apparatus, G. T. Dixon..... 591,387
Car roof, T. Eubank..... 591,665
Car starter, G. D. Rowell..... 591,498
Carbon holder for arc lights, O. S. Moss..... 591,486
Carousel, P. J. Spracklen..... 591,507
Case. See Pocket case.
Cash register, E. Ensworth..... 591,748
Casket, H. T. Loomis..... 591,781
Centrifugal machine, J. Laidlaw..... 591,770
Checkrein fastener, H. J. Ellers..... 591,622
Cheese rack, J. Levey..... 591,671
Chopper. See Cotton chopper. Food chopper.
Churn, O. B. Paulsen..... 591,493
Cigar tip cutter and match box and lighter, S. E. Ball..... 591,523
Cigarette holder, G. Hara..... 591,471
Clamp. See Stovepipe clamp. Velocipede saddle clamp.
Clamp, Palmer & Mercer..... 591,421
Clothes line holder, H. Catlin..... 591,735
Coal handling device, H. N. Flidner..... 591,596
Coffee warmer, F. J. Park..... 591,786
Coin freed goods delivery apparatus, J. Turner-Turner..... 591,511
Collar, horse, J. H. Hainsworth..... 591,518
Corset, C. E. Woodworth..... 591,518
Corset and abdominal supporter, I. Friedman..... 591,626
Cotton chopper, D. A. Yarbrough..... 591,715
Couch, adjustable, Googins & Howarth..... 591,530
Coupling. See Car coupling. Magnetic coupling.
Crank, See Sand crank. Thill coupling.
Cradle, J. R. Garrett..... 591,465
Crane, T. James..... 591,650
Cultivator, E. V. Burrow..... 591,589
Cultivator, disk, C. B. Miller..... 591,484
Curtain pole, F. S. Miley..... 591,674
Curtain shaft, A. B. Dunn..... 591,389
Cutter. See Cigar tip cutter. Endless chain cutter. Fodder cutter.
Cyanids, making, J. R. Moise..... 591,675
Cyclometer, E. Hart..... 591,761
Cylinder lock, grand master key, H. G. Voight..... 591,762
Damper regulator, C. C. Kealy..... 591,458
Damper regulator, F. T. Mueller..... 591,562
Dental mallet, electric, P. Russell..... 591,499
Derrick, farm, P. N. Swanson..... 591,612
Desk and seat, school, F. C. Cheney..... 591,738
Digger. See Potato digger.
Dish drainer..... 591,494
Disinfecting compound and apparatus for applying, Oppermann & Goehde..... 591,683
Disintegrating machine, G. H. Pond..... 591,494
Display cover, barrel, W. J. Tanner..... 591,661
Display rack, umbrella, U. G. Rockwell..... 591,572
Display table, C. A. Shaffer..... 591,661
Diving apparatus, B. Nelson..... 591,773
Door check, F. C. Fisher..... 591,751
Door jamb, metallic, J. P. Buchanan..... 591,620
Door, screen, J. Fritz..... 591,550
Dough mixing machine, J. Ballus..... 591,722
Drier. See Sand drier.
Dry closet, E. W. Anthony..... 591,582
Duplex engine, H. B. Gale..... 591,529
Dye, trisazo, M. Boniger..... 591,616
Eaves trough, C. J. Swink..... 591,705
Electric heater, O. D. McClellan..... 591,783
Electric machine, dynamo, E. W. Farnham..... 591,623
Electric meter, G. A. Scheffer..... 591,625
Electric switch, J. C. Cassidy..... 591,451
Electric switch, J. W. Parkin..... 591,491
Electrical protector, C. A. Rolfe..... 591,426
Electrolyzing, process of and apparatus for, W. Bein..... 591,730
Elevator, G. H. Tuttle..... 591,578
Embossing machine, M. V. B. Howe..... 591,473
End gate, wagon, E. E. Hanken..... 591,531
Endless chain cutter, T. E. Martin..... 591,606
Engine. See Air engine. Compressing engine. Duplex engine. Gas engine. Steam engine.
Engines, igniter for gas or gasoline, M. O. Godding..... 591,598
Engines, regulating apparatus for air compressing, H. Bourne Hansen..... 591,583
Envelope, H. A. Morey..... 591,415
Envelope opener, B. F. Lantz..... 591,651
Evaporating pan, W. Musselwhite..... 591,678
Exhibitor, wall paper, F. W. Chickering..... 591,453
Exudation cap, J. W. Tallmadge..... 591,434
Fan attachment, J. S. Bailey..... 591,731
Fan holder, E. W. R. Poekert..... 591,423
Fastening driving mechanism, W. Shaw..... 591,730
Faucet, P. K. O'Lally..... 591,785
Faucet, H. Peter..... 591,686
Feed table, W. H. McFadden..... 591,563
Fence, C. A. Benner..... 591,732
Fence, D. D. Frisbee..... 591,632
Fence, L. D. Harden..... 591,760
Fence, W. F. Sheldon..... 591,428
Fence, hedge, L. Young..... 591,716
Fence, hedge, L. W. Young..... 591,717
Fence, wire, T. M. Guest..... 591,470
Fence, wire, S. Roseman..... 591,708
File, H. A. Beltz..... 591,448
Fire alarm, S. W. Ludlow..... 591,408
Fire alarm, thermic, K. O. Slosky..... 591,700
Firearm, recoil operated, A. Burgess..... 591,525
Floors for buildings, construction of concrete, W. H. Jenkins..... 591,405
Fluid pressure brake, H. S. Smith..... 591,701
Fodder cutter, J. Dick..... 591,591
Food chopper, L. T. Snow..... 591,575
Fork. See Hay fork.
Frame. See Light frame.
Furnace. See Shaft or blast furnace.
Furnaces, apparatus for feeding bagasse, sawdust, etc., to, J. Fisher..... 591,752
Gage. See Slide gage.
Galvanic battery, C. B. Schoenmehl..... 591,427
Game apparatus, F. Andriot..... 591,784
Game apparatus, C. B. Camburn..... 591,737
Gas engine and generator, D. Best (reissue)..... 11,633
Gas lights, material for hoods or mantles for incandescent, W. L. Voelker..... 591,438
Gas vending machine, coin controlled, W. Webber..... 591,514
Gate. See Railway gate.
Gate, J. Lane..... 591,780
Gate, G. W. Pettit..... 591,687
Generator. See Blast generator. Steam generator.
Gold from ores, process of and apparatus for extracting, L. C. Daumas..... 591,527
Governor, engine, F. H. & B. C. Ball..... 591,447
Grate, J. T. Glover..... 591,487
Griddle, T. A. Watrous..... 591,513
Half tone screen, M. Levy..... 591,663
Handle. See Tool handle.

(Continued on page 270)

Advertisements.

ORDINARY RATES.

Inside Page, each insertion, - 75 cents a line
Back Page, each insertion, - - \$1.00 a line

For some classes of Advertisements, Special and Higher rates are required.

The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may head advertisements at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at Publication Office as early as Thursday morning to appear in the following week's issue.

WOOD or METAL WORKERS
without steam power can save time and money by using our
Foot and Hand Power Machinery
SEND FOR CATALOGUES—
A—Wood-working Machinery.
B—Lathes, etc.
SENECA FALLS MFG. COMPANY,
695 Water St., Seneca Falls, N. Y.

ROTARY PUMPS AND ENGINES:
Their Origin and Development.—An important series of papers giving a historical resume of the rotary pump and engine from 1588 and illustrated with clear drawings showing the construction of various forms of pumps and engines, 38 illustrations. Contained in SUPPLEMENTS 1109, 1110, 1111. Price 10 cents each. For sale by Munn & Co. and all new dealers.

POWER & FOOT LATHES. SHAPERS, PLANERS, DRILLS, MACHINE SHOP OUTFITS, TOOLS AND SUPPLIES. CATALOGUE FREE.
SEBASTIAN LATHE CO. 120 CULVERT ST. CINCINNATI, O.

Pipefitters!
Your kit is not complete unless it includes the famous
STILLSON WRENCH
which is particularly adapted for turning out the best work without crushing the pipe in the least. All parts are drop-forged. Once tried it is always used. It has many imitations but no equals. See explanatory cuts. Price list on application to
WALWORTH MFG. CO., 20 Oliver Street, Boston, Mass.

GATES ROCK & ORE BREAKER, Steam Ore Stamp, Mining Machinery,
50 years experience as builders.
GATES IRON WORKS,
Dept. C, 650 Elston Ave., Chicago.

DRY BATTERIES.—A PAPER BY L. K. Bohm, treating of open circuit batteries, historical dry batteries, modern dry batteries, Hellesen's battery, Bryan's battery, Koller's battery, and the efficiency of dry cells. With three illustrations. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 1001. Price 10 cents. To be had at this office and from all new dealers.

TRANSITS AND LEVELING INSTRUMENTS.
PLUMBERS' IRON LEVEL With Double Plumb.
Special device for finding rise and fall of all piping. Price \$2.25. Size 12 inch. For book on the level
C. F. RICHARDSON & SON,
P. O. Box 977, ATHOL, MASS., U. S. A.

Fluting, Grooving and Channeling
can be most quickly, easily and accurately done by using the
RIVETT LATHE
(Eight-inch Precision Lathe with Traverse Miller). Mills and grinds work the whole length of lathe. Easy to adjust. Does more and better work than any other machine.
FANEUIL WATCH TOOL CO., Boston, Mass., U. S. A.

Eyelet Machines.
We can furnish the Latest Improved Eyelet Machines for making shoe eyelets and special eyelets of all descriptions. We are also builders and designers of Special Wireworking Machinery.
Send for Circular.
BLAKE & JOHNSON,
P. O. Box 7, WATERBURY, CONN., U. S. A.

WELL DRILLING MACHINERY,
MANUFACTURED BY
WILLIAMS BROTHERS,
ITHACA, N. Y.
MOUNTED ON OR SILLS, FOR DEEP OR SHALLOW WELLS, WITH STEAM OR HORSE POWER
SEND FOR CATALOGUE
ADDRESS WILLIAMS BROS. ITHACA, N. Y.

The Berkefeld House Filter.
The only Filter Removing Typhoid and Cholera Bacilli. Tested and indorsed by many leading authorities in Europe and America. It gives a continuous flow of filtered water, absolutely free from germs. It is easily cleaned, as all impurities remain on the surface of the filtering cylinder. Cylinders can be sterilized by boiling in water for one hour. Send for circular and prices to the Berkefeld Filter Co., 4 Cedar St., New York
See Illus. Article in Scientific American, June 23, 1894.

CATALOGUES FREE TO ANY ADDRESS
GEARS AND PARTS OF MODELS
GOODNOW & WIGHTMAN

ARMSTRONG'S No. 0 THREADING MACHINE
Can be attached to bench or post. Designed for threading the smaller sizes of pipe, iron or brass, also bolts. Has two speeds, one for pipe 1/4 to 1 inch; the other for pipe 1 1/4 to 2 inches, inclusive. Uses the regular Armstrong adjustable dies. Other attractive features. Send for particulars. The Armstrong Mfg. Co., 139 Centre Street, New York. Bridgeport, Conn.

Handle, J. O'Neill	591,547
Harrow, disk, P. E. Little	591,555
Harvesters, knotting mechanism for self-binding, J. F. Appleby	591,614
Harvesters, segmental conveyor for potato, A. T. Dowden	591,388
Hat, Gammons & Bracher	591,755
Hat brims, machine for attaching bindings to curled or rolled, Gammons & Bracher	591,754
Hay fork, automatic harpoon, J. L. Ritter	591,609
Hay rake, horse, C. O. Lyce	591,672
Heat insulating article, Lumley	591,409
Heat or dam per regulator, J. F. Burley	591,526
Heater. See Electric heater. Water heater.	
Hinge, lock, A. Rentsch	591,693
Hoe, J. F. Vernicke	591,710
Hook. See Belt hook. Snap hook.	
Hooping machine, barrel, A. T. S. Roebbling	591,497
Horse detacher, G. Grebe	591,797
Horse foot protector, J. W. Thurlow	591,510
Horse governor or chin rest, C. S. Baum	591,726
Horsehoe, elastic, P. H. Graves	591,601
Hose fastening, E. E. Gold	591,468
Hose fitting, J. O. De Wolf	591,736
Hub attaching device, R. Lord	591,481
Humidifier, Thompson & Sohoni	591,576
Hydrocarbon burner, G. C. Roberts	591,694
Ice cream mould and disher, T. F. Rankin	591,635
Incaudescence, J. De la Motte	591,652
Indicator. See Station indicator.	
Indicator and recorder, E. L. Morgan	591,416
Jack. See Lifting jack.	
Jar. See Preserve jar.	
Jug, W. M. Brewer	591,735
Kitchen cabinet, F. Washington	591,449
Ladder and duplex step therefor, L. W. Noyes	591,418
Lamp, F. A. Morse	591,417
Lamp burner, gasolene, A. M. Southard	591,506
Lamp chimney attachment, R. L. & L. P. Moore	591,677
Lamp fitting, glow, F. Palm	591,490
Lamp holder, E. C. Holmes	591,515
Lamp or lantern extinguisher, D. T. K. McEwen	591,608
Lamps, system of lighting for hydrocarbon, R. L. Doran	591,622
Land roller, Middleton & Loomis	591,414
Lantern, C. Hamm	591,647
Latch, P. F. Fleming	591,510
Latch, gate, O. Bowser	591,586
Leather preparatory to dyeing, treating, E. Koester	591,769
Lens, I. Gathmann	591,496
Letter or character for signs, E. J. Lutwyche	591,536
Lettering device, L. Rust	591,607
Lifting jack, G. W. Turner	591,738
Lingo, H. Rigby	591,496
Lock. See Cylinder lock. Seal lock.	
Lock, J. J. Link	591,479
Locking drawers of cabinets, device for, D. E. Hunter	591,552
Loom, B. Bosse	591,734
Luggage carrier, J. H. Quinton	591,425
Magnetic coupling, T. J. Fay	591,395
Mail bag holding and catching device, C. M. Bennett et al.	591,731
Match box, Barker & Colburn	591,379
Metals from their solutions, process of an apparatus for electrolytic recovery of, Richards & Roepper	591,571
Meter. See Electric meter.	
Mill. See Rolling mill. Windmill.	
Mining machine, J. Blake	591,449
Mould. See Ice cream mould.	
Moulding apparatus, L. Fingal	591,463
Moulding machine, W. Zoeller	591,520
Mower, lawn, S. P. Townsend	591,435
Mowing machine, C. A. Patten	591,567
Musical instrument, Phillips, C. Henery	591,473
Nailing machine, S. W. Robinson	591,558
Oar lock, J. R. Supple	591,509
Oil purifier, W. C. Fahy	591,394
Oiling device for journals, self, C. H. C. Koch	591,406
Ophthalmoscope, J. T. Bryant	591,617
Packing, metal, W. Law	591,670
Pan. See Evaporating pan.	
Paper covered vessels, manufacture of, U. Hull	591,404
Paving blocks, apparatus for constructing, A. B. Greig	591,757
Pedal toe clip, Osmond & Housman	591,685
Piano technical regulator, F. B. Biddle & Westlin	591,800
Picture displaying device, P. S. Chance	591,452
Pile drivers, etc., supporting wheel for, B. Goldsbrough	591,756
Piston, C. G. Evans	591,392
Plane, J. A. Traut	591,662
Plane, A. T. De Wolf	591,663
Planter, J. D. Tinnin	591,628
Planter, potato, J. P. Davenport	591,676
Plow, orchard or vineyard, F. Moore	591,676
Plow, wheeled, Kerns & Head	591,535
Pocket book, combination, D. Dusart, Jr.	591,746
Pock cake, V. Schumann	591,548
Popcorn cakes machine, W. K. Eaton	591,461
Potato digger, J. Schwartz	591,642
Pottery moulding machine, J. A. Zengler	591,580
Power. See Tread power.	
Precious metals by solution, obtaining, E. J. Fraser	591,753
Preserve jar, F. Dedreux	591,740
Press, O. Smith	591,702
Printing press feed table and feeder, C. G. Harris	591,648
Printing press, device, Harris & McNutt	591,649
Propelling boats, men, J. H. Baker et al.	591,644
Pulp grinder, wood, J. H. Baker et al.	591,644
Pulp screen, J. H. Baker et al.	591,645
Pump, rotary, I. Artemkin	591,522
Pumping apparatus, water, M. T. Chapman	591,382
Puzzle, J. H. Stauber	591,639
Rack. See Cheese rack. Display rack.	
Rail bond, electrical, W. H. Wiggin	591,516
Rail fastener, B. Ferriss	591,750
Railway, T. M. Galbreath	591,597
Railway, electric, Urquhart & Wynne	591,456
Railway gate, W. Martin	591,556
Railway gate, automatic, H. Wetmarshausen	591,441
Railway signaling, A. C. T. Bond	591,376
Railway sleeper, Owen & Bates	591,565
Railway switch, street, D. W. & G. W. Hatfield	591,628
Railway switch tongue rail, Martin & Price-Williams	591,412
Railway vehicle window, J. A. Normand	591,680
Range, reversible, W. P. Lewis	591,654
Reel. See Tape reel.	
Refrigerator, S. W. Bates	591,374
Refrigerator, market, Harrison & Kelley	591,401
Refrigerator, O. Andrews	591,591
Register. See Cash register.	
Regulator. See Damper regulator. Heat or damper regulator.	
Rod coupling device, A. C. Ponkney	591,690
Roller. See Lane roller.	
Rolling mill, J. S. Worth	591,712
Rolling mill plate turner, J. S. Worth	591,712
Rolling pipe couplings, apparatus for, De Forest & Kenna	591,742
Roof bracket, J. Matter	591,772
Rope adjusting device, J. B. Biddle	591,456
Saddle, pneumatic harness, Schorp & Sigling	591,659
Sail slide, C. H. Worthen	591,446
Sand drier, Merriman & Vought	591,413
Sash and window screen hanger and operator, storm, J. D. Brainard	591,799
Sash cord fastener, Byrke & Petersen	591,589
Sash fastener, J. M. Graham	591,468
Sash fastener, W. J. Neidl	591,537
Saw set, J. A. Kidwell	591,478
Scale, computing, I. C. Koehne	591,629
Scale, weighing, F. R. Moser	591,657
Scoop, potato, W. A. Reddick	591,691
Scraper, dumping, M. G. Bunnell	591,378
Screen. See Half tone screen. Pulp screen.	
Window screen.	
Seal lock, Lee & Hoyt	591,407
Sewing machine, D. H. & J. Agan	591,718
Sewing machine, L. Onderdonk	591,420
Sewing machine, overedge, J. T. Collins	591,383
Sewing machine, overedge, J. T. Collins et al.	591,384
Sewing machine quilting attachment, W. Obuch	591,784
Sewing machine, sole, H. I. Illingworth	591,475
Sewing machine table top, N. A. Hull	591,474
Sewing machine take up mechanism, L. Onderdonk	591,546
Shaft coupling, vehicle, W. A. Jackman	591,764
Shaft locking device, A. G. Mather	591,558
Shaft or blast furnace, F. Burgers	591,524
Shed, vehicle, W. H. B. Hallock	591,339
Sheet metal apparatus for removing scale from	
Davies & Thomas	591,621
Ship's light and air port, T. Utley	591,707
Shoe stretcher, C. L. Passmore	591,492
Shutter fastener, J. Bannan	591,723
Skylight frame, C. W. Stran	591,601
Slat cleaning device, J. G. Shaw	591,601
Sleigh, J. N. Runions	591,640
Slide gate, E. Weber	591,709
Snap hook, C. A. Skeels	591,429
Snow guard, H. M. Esselen	591,594

(Continued on page 271)

STEAM ENGINEERING

(Stationary, Locomotive, Marine); Mechanical Drawing; Architectural Drawing; Machine Design; Electricity; Architecture; Plumbing; Railroad; Electrical; Bridge and Highway Engineering; Surveying and Mapping; Metal Pattern Cutting; Bookkeeping; Shorthand; English Branches; Mining; Metal Prospect'g. All who **GUARANTEED SUCCESS.**
Fees Moderate, Advance or Installments.
Circular Free; State subject you wish to study.
International Correspondence Schools, Box 942, Scranton, Pa.

\$15 course in mech. drawing at Rockton Correspondence School of Mech. Engineering, Little Falls, N. Y., will make you a proficient draughtsman

This beats Wind, Steam, or Horse Power. We offer the
WEBSTER 2 1/2 actual horse power GAS ENGINE
for \$150, less 10% discount for cash. Built on interchangeable plan. Built of best material. Made in lots of 100 therefore we can make the price. Boxed for shipment, weight 800 pounds. Made for Gas or Gasoline.
Write for Special Catalogue.
WEBSTER MFG CO.,
1074 West 15th Street, CHICAGO.

HOISTING ENGINES

operating on GASOLINE, DISTILLATE or RUDE OIL. Both Friction and Geared Hoist, from 10 to 50 H. P. for Mines, Quarries, Docks, etc. Great Saving over steam, especially where wood, coal or water are scarce. Send for catalog. Guaranteed fully. State size wanted. Address **Weber Gas and Gasoline Engine Co.,** 412 S. W. Boulevard, Kansas City, Mo.

SCIENTIFIC AMERICAN SUPPLEMENT.—Any desired back number of the SCIENTIFIC AMERICAN SUPPLEMENT can be had at this office for 10 cents. Also to be had of new dealers in all parts of the country.

"WOLVERINE"
GAS & GASOLINE ENGINES
STATIONARY AND MARINE.
The "Wolverine" is the only reversible marine gas engine on the market. It is the lightest engine for its power. Requires no licensed engineer. Absolutely safe. Manufactured by
WOLVERINE MOTOR WORKS,
12 Huron St., Grand Rapids, Mich.

VAPOR LAUNCH Complete for \$150.

ROW, SAIL and STEAM BOATS. for \$150.
Send five cents for Catalogue.
RACINE YACHT AND BOAT WORKS,
Racine Junction, Wis., Box A.

50 Per Cent Increase at no additional expense.

VICTOR VAPOR ENGINE.
Local Agents Wanted.
Steam and Vapor Launches, Row and Sail Boats.
Send for catalogue. Specify one wanted.
THOS. KANE & CO.,
64-86 Wabash Ave., Chicago.

ALCO VAPOR LAUNCH

Motor controlled from bow. Valve movement, 12 to 1. 16 to 60 ft. Launches. Twin Screws a specialty. 1, 2, 3, 5, 7, 12, 14 and 20 h. p. No licensed engineer or pilot required. Speed and safety guaranteed. No dangerous Naphtha or Gasoline used. No disagreeable vibration.
Send 10 cents in stamps for 1897 Catalogue.
Marine Vapor Engine Co., ft. Jersey Av., Jersey City, N. J.

THE MACHINERY OF A NAPHTHA Launch.—A detailed description of the motive power of a Modern Naphtha Launch, with sectional views showing all the parts of the boiler and engine. A most valuable paper. 4 illustrations. Contained in SUPPLEMENT 1104. Price 10 cents. For sale by Munn & Co. and all new dealers.

OLDS ENGINE
Has no moving parts in mixing device. No gears or levers. The two popper valves are operated in straight line by plain eccentric from main shaft. Mechanically correct. Indorsed by economists.
Does not balk in either warm or cold weather. 1 to 50 horse power.
P. F. Olds & Son Engine Works, Box 418, Lansing, Mich.

HAWKINS' NEW CATECHISM OF ELECTRICITY

A PRACTICAL TREATISE for Engineers, Electricians, Wiremen and Amateurs. 560 pages 300 illustrations, bound in leather, pocketbook form, gold titles and edges. Strictly "Up-to-Date." Postpaid, \$2.00. THEO. AUEL & CO., 63 Fifth Avenue, New York.

A. W. FABER

Manufactory Established 1761.
LEAD PENCILS, COLORED PENCILS, SLATE PENCILS, WRITING SLATES, STEEL PENS, GOLD PENS, INKS, PENCIL CASES IN SILVER AND IN GOLD, STATIONERS' RUBBER GOODS, RULERS, COLORS AND ARTISTS' MATERIALS.
78 Reade Street, - - - New York, N. Y.
Manufactory Established 1761.

HARDTMUTH'S "KOH-I-NOOR" COPYING PENCILS
ARE THE BEST PENCILS MANUFACTURED IN THE WORLD. EVERY ARCHITECT, DRAUGHTSMAN, ENGINEER, COPIST, CLERK, AND EVERY ONE USING PENCILS SHOULD TRY THE
"KOH-I-NOOR"
ONCE TRIED, ALWAYS USED THEREAFTER!
FOR SALE BY ALL STATIONERS AND ARTISTS' MATERIAL DEALERS. SAMPLE FREE ON APPLICATION.
FAVOR, RUHL & CO. IMPORTERS,
121 WEST HOUSTON ST. NEW YORK.

KRAFTUBERTRAGUNGSWERKE RHEINFELDEN. Society for the Utilization of the Water Power of the Rhine N/Bale, Switzerland. 16,800 H. P. NOW AVAILABLE. TO BE INCORPORATED TO 30,000 H. P. The Company is in a position to let electric energy at exceptionally cheap rates and on the most favorable terms. They also offer to applicants wishing to establish themselves near the works, suitable land on either the German (Badish) or the Swiss side of the Rhine, in the vicinity of important railway lines. Cheap labor.
For further information please address The Manager, Kraftubertragungswerke, Rheinfelden, Switzerland.

Shaving—Easy—Safe—Luxurious.
WITH WILLIAMS' SHAVING SOAPS
THE ONLY REAL SHAVING SOAPS
SOLD EVERYWHERE.
Williams' Shaving Stick, 25 cts.
Genuine Yankee Shaving Soap, 10 cts.
Luxury Shaving Tablet, 25 cts.
Swiss Violet Shaving Soap, 50 cts.
Jersey Cream (Toilet) Soap, 15 cts.
Williams' Shaving Soap (Barbers'), 6 Round Cakes, 1 lb., 40c. Exquisite 150 for toilet. Trial cake for 2c. stamp.
THE J. B. WILLIAMS CO.,
GLASTONBURY, CONN.
LONDON, 64 GREAT RUSSELL ST. W.C. SYDNEY, 161 CLARENCE ST.

50 YEARS' EXPERIENCE

PATENTS
TRADE MARKS
DESIGNS
COPYRIGHTS & C.
Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. Handbook on Patents sent free. Oldest agency for securing patents. Patents taken through Munn & Co. receive special notice, without charge, in the
Scientific American.

A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, \$3 a year; four months, \$1. Sold by all new dealers.
MUNN & Co., 361 Broadway, New York
Branch Office, 625 F St., Washington, D. C.

A New Static and Large
COIL X RAY TUBE
Highest efficiency obtained
Send for illus. catalogue of X Ray Supplies.
Kirmayer & Oelling, 17 Bromfield St., Boston, Mass.

The Queen Acme No. 5 Microscope

NEW MODEL AS PER CUT.
The Ideal Microscope for Amateur Research. Stands unequalled for precise and accurate adjustments and optical excellence. With objectives giving from 50 to 500 diameters, in case, \$35.00.
Send for new Microscope Catalogue B. M.
QUEEN & CO., Inc.,
1011 Chestnut St., Philadelphia, Pa.

GOLD SAVED by sending for my 1897 Catalogue and Discounts on Architectural, Building, Mechanical, Electrical, Scientific and Technical Books. W. M. T. COMSTOCK, 23 Warren St., New York.

Arithmetic of Electricity

By Prof. T. O'CONOR SLOANE.
138 Pages, Illustrated, Price \$1.00

A PRACTICAL Treatise on Electrical Calculations of all kinds reduced to a series of rules, all of the simplest forms, and involving only ordinary arithmetic; each rule illustrated by one or more practical problems, with detailed solution of each one. Followed by an extensive series of Tables, including the following subjects: All Kinds of Units of Measurement of Electrical and Mechanical Work, Energy and Heat; Relations of Different Systems of All Kinds of Units; Relation of Different Wire Gauges, of Wire of Different Sizes; Specific Resistances; Thermo-chemical and Electro-chemical Equivalents; Useful Factors, etc., etc.
This book may be classed among the most useful works published on the science of electricity, covering, as it does, the mathematics of electricity in a manner that will attract the attention of those who are not familiar with algebraical formulae.

We can also furnish Prof. Sloane's works on electricity as follows:

Arithmetic of Electricity, 138 pages.....\$1.00
Electric Toy Making, 140 pages..... 1.00
How to Become a Successful Electrician, 189 pages..... 1.00
Standard Electrical Dictionary, 682 pages..... 3.00
Electricity Simplified, 158 pages..... 1.00

The above five volumes, comprising a COMPLETE ELECTRICAL LIBRARY, sold at the special reduced price of \$5.00 put up in a neat folding box. You save \$2.00 by ordering the set complete. Five volumes 1,300 pages, over 450 illustrations.

Send for special circular containing full table of contents of the above books.

MUNN & CO., 361 Broadway, New York.

Snow plow, Smith & White.....	591,432
Sole leveling machine, E. C. Judd et al.....	591,766
Sole rounding machine, E. Erickson.....	591,533
Sounding board, H. A. Hambloch.....	591,759
Splice ear, mechanical, H. H. Luscomb.....	591,556
Spool holder, O. E. Longwell.....	591,605
Stall, portable, D. Stitzer.....	591,732
Stamp box, J. H. McNeill.....	591,679
Stamping apparatus, D. B. Morison.....	591,560
Stand. See Washstand.....	
Station indicator, J. A. Mangold.....	591,410
Steam boiler, water tube, E. E. Wigzell.....	591,444
Steam engine, M. R. Moore.....	591,485
Steam generator, G. F. Dinsmore.....	591,460
Stereotype plates, bed block for, C. Pieper.....	591,422
Stone channeling machine, A. C. Backus.....	591,615
Stone planing machine, J. Mann.....	591,411
Stopper. See Bottle stopper.....	
Stopper neck, G. W. Martin.....	591,782
Stovepipe clamp, F. H. Livingston.....	591,480
Stovepipe elbow making machine, J. Russell.....	591,776
Switch. See Electric switch.....	
Switch apparatus, J. P. Coleman.....	591,530
Table. See Display table.....	
Table canopy, dining, D. V. Davis.....	591,457
Tape reel, J. G. Eddy.....	591,747
Telegraph key, E. W. Farman.....	591,624
Thill coupling, Moyer & Graf.....	591,561
Thread severing attachment for spools, W. H. Earle.....	591,592
Tire, bicycle, J. D. Parker.....	591,787
Tire, bicycle, C. H. Stevens.....	591,791
Tire, pneumatic, O. S. Hammond.....	591,551
Tire tube, J. E. Davis.....	591,438
Tire, woven, R. Cowen.....	591,456
Tires, device for inserting tubes in pneumatic, C. McClure.....	591,607
Tires, means for mending inner tubes of bicycle, A. V. Schorr.....	591,501
Tires, means for repairing pneumatic, C. J. Johnson.....	591,477
Tires, needle for repairing punctures in bicycle, C. F. White.....	591,443
Tobacco stemming machine, J. B. Underwood.....	591,436
Tool, combination, C. J. Armstrong.....	591,720
Tool, combination, A. C. Ponkney.....	591,689
Tool handle, C. A. Vaughn.....	591,512
Torpedo steering apparatus, E. Kaselowsky.....	591,768
Toy, musical, J. A. Irving.....	591,476
Trace carrier, J. Schilling.....	591,610
Transom lifter, H. W. Pierce.....	591,569
Transporting granular or similar materials, device for, A. Rothenbach.....	591,696
Trap. See Animal trap.....	
Trap and pipe coupling, N. E. Smith.....	591,431
Trap power, C. Search.....	591,690
Trolley, G. L. Shryock.....	591,638
Trolley wheel, R. S. McPhail.....	591,489
Trough. See Eaves trough.....	
Type bars, machine for making, C. Sears.....	591,777
Type, process of and apparatus for casting print, ing, J. J. Smith.....	591,430
Typewriting machine, J. C. Landis.....	591,669
Typewriting machine tabulating attachment, H. B. Schneider.....	591,789
Umbrella closing device, J. B. Riehl.....	591,637
Valve, relief, J. H. Beare.....	591,375
Vehicle, J. C. Bonner.....	591,730
Vehicle brake hanger, S. D. Ross.....	591,686
Vehicle, motor, G. H. Grenlich.....	591,398
Vehicle steering mechanism, motor, C. A. Faure.....	591,595
Vehicle wheel, G. W. C. Lomb.....	591,771
Velocipede saddle clamp, M. M. Deem.....	591,749
Vending device, M. B. Mills.....	591,741
Vessel, marine, G. Esplan.....	591,737
Veterinary eraser, F. F. Hoffmann.....	591,403
Washboard, W. H. Osmer.....	591,684
Washboard, J. H. Stratman.....	591,704
Washing machine, W. Baylis.....	591,728
Washing machine, G. W. Spenser.....	591,643
Washing machine, J. H. Verity.....	591,437
Washstand, B. Badanes.....	591,664
Water closet, W. T. Fox.....	591,397
Water heater, A. Buerkle.....	591,588
Water heater and purifier, Shepard & Whitlock.....	591,505
Water race rack cleaner, R. S. Judson.....	591,707
Water tower, Henning & Pigott.....	591,603
Weed destroyer, P. E. Erickson.....	591,391
Wheel. See Trolley wheel.....	
Wheel, D. Fahey.....	591,393
Wheels, rim for pneumatic tired, J. Pearson.....	591,568
Wheels to hubs, axles, or shafts, fastening, G. E. Straus.....	591,798
Whiffletree fastening, W. H. Bayley.....	591,727
Whistle for gas or gasoline engines, G. F. Arp.....	591,521
Windmill, H. M. Peterson.....	591,775
Window screen, E. A. Worthen.....	591,714
Wire stretching implement, A. B. Probasco.....	591,495
Wire swaging machine, L. Cook.....	591,454
Woodworking machine, W. Postmus.....	591,424
Wrench. See Adjustable wrench.....	
Wrench, J. B. Ford.....	591,528
Wrench, R. Hagstrom.....	591,779
Wrench, J. H. Johnson.....	591,563

DESIGNS.

Bath tub, D. D. Buick.....	27,725
Bicycle saddle, C. E. Stanley.....	27,730
Bracket, wall, H. Krauth.....	27,728
Bread pan, I. Hirsch.....	27,722
Burner tube, L. T. Alton.....	27,720
Chair, D. W. Kendall.....	27,727
Cork extractor, H. Streiff.....	27,715
Cradle frame, R. W. Haggard.....	27,726
Game board, C. H. Leonard.....	27,733
Golf club, J. H. Adams.....	27,732
Knife blade, C. Webster.....	27,745
Lantern, F. T. Williams.....	27,717
Monument, E. O. Townsend.....	27,729
Shade roller axle, T. P. Brown.....	27,719
Spectacle bridge, G. A. Bader.....	27,712
Stove, Bascom & Ambrose.....	27,724
Stove or range, G. W. Cope.....	27,723
Tire, E. G. Van Zandt.....	27,731
Trace guard, Sutterlin & Schilling.....	27,718
Tray or similar article, G. E. Waldeck.....	27,714
Watchmaker's tool, H. Zimmern.....	27,713
Water heater section, J. A. Rathbone.....	27,721

TRADE MARKS.

Bicycle pedals, White Sewing Machine Company.....	30,683
Blacking, boot and shoe, Herriott Brothers & Company.....	30,675
Blackings and dressings, stains, and waxes, boot, shoe, and leather, Herriott Brothers & Company.....	30,676
Blue, washing, J. & J. Colman.....	30,674
Canned goods, certain named, Portland Packing Company.....	30,661
Canned lobster, Muntwyler & Dubler.....	30,660
Cheese, Probst & Company.....	30,662
Cocoa-oatmeal preparations, M. Michaleis & S. O. Coffe.....	30,659
Coffee, mixture sold as a substitute for, H. D. Chipman.....	30,670
Corn flakes, Indian, J. D. Hage & Company.....	30,666
Corn meal and grits, Indian, J. D. Hage & Company.....	30,665
Crackers and cakes, United States Baking Company.....	30,663
Drink tablets, W. I. Davenny.....	30,671
Flour, C. King & Son.....	30,668
Flour, wheat, Wm. S. Hills Company.....	30,667
Foods for infants and invalids, T. J. Turner.....	30,664
Injectors, Penberthy Injector Company.....	30,682
Leather, artificial, Boston Artificial Leather Company.....	30,680
Medicines and remedies, homeopathic, Bronx Chemical Company.....	30,679
Oils, water-proof compounds, lubricants, greases, and petroleum products, Charles Efron Company.....	30,677
Picture apparatus, moving, American Mutoscope Company.....	30,681
Putty, stone, E. F. Meyer.....	30,678
Soap, A. R. Brandy.....	30,673
Tooth washes, Opal Creme Company.....	30,672

PRINTS.

"The Kimball Situation," W. W. Kimball Company.....	54
---	----

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1883, will be furnished from this office for 10 cents. In ordering please state the name and number of the patent desired, and remit to Munn & Co., 361 Broadway, New York. Special rates will be given where a large number of copies are desired at one time.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list, provided they are simple, at a cost of \$40 each. If complicated the cost will be a little more. For full instructions address Munn & Co., 361 Broadway, New York. Other foreign patents may also be obtained.

How to Build a Home



Those intending to build will find the very best practical suggestions and examples of Modern Architecture in the handsomest Architectural Magazine ever published . . .

"The Scientific American Building Edition."

Each number is illustrated with a Colored plate and numerous handsome engravings made direct from photographs of buildings, together with interior views, floor plans, description, cost, location, owners' and architects' names and addresses. The illustrations include seashore, southern, colonial and city residences, churches, schools, public buildings, stables, carriage houses, etc.

All who contemplate building, or improving homes or structures of any kind, have in this handsome work an almost endless series of the latest and best examples from which to make selections, thus saving time and money.

PUBLISHED MONTHLY. SUBSCRIPTIONS \$2.50 A YEAR. SINGLE COPIES 25 CENTS. Semi-Annual Bound Volumes, \$2.00 each. Yearly Bound Volumes, \$3.50 each.

For sale at all news stands, . . . or address **MUNN & CO., Publishers, 361 Broadway, New York**

CARBORUNDUM
HARDEST ABRASIVE KNOWN. EMERY AND DIAMOND POWDER SUBSTITUTE. IN FLOUR, POWDER-CRYSTAL-WHEEL-SLAB & HOME FORM. CARBORUNDUM CO. NIAGARA FALLS, N.Y. U.S.A.

\$45 Plating Dynamo for 50 gallons Nickel Solution. Dynamos for light and Electric Motors for power. All sizes, best construction and sold on easy payments. State what you want. The Hobar Electric Manufacturing Co., Troy, Ohio.

IF YOU WANT TO LAUGH, send 10 Cents for the **DONKEY PUZZLE**. Send for Illus. Catalogue.

CHAFFEE & SELCHOW, Manufacturers of GAMES, TOYS, NOVELTIES, etc. 451-455 W. 125th St., New York City.

WOODEN TANKS. For Railroads, Mills and Manufactories. Builders of Steel Towers and Tanks. La. Red Cypress Wood Tanks a specialty. **W. E. CALDWELL CO.,** 217 E. Main Street, Louisville, Ky.

IMPROVED WASHBURN'S PATENT COLLAR FASTENER AND BACHELOR'S BUTTON
A Collar Fastener that is better than button or stud. Saves wear and tear on buttonholes. Easily applied. The Bachelor's Button is the handiest thing ever invented. Saves sewing. Can be adjusted instantly when needed. Easily detachable from garments. Samples of either, by mail, for 10 cents. Illus. catalogue free.

AMERICAN RING CO., Box P, Waterbury, Conn.

TYPEWRITERS HALF PRICE
We will sell you any typewriter made for one half regular price, many for one quarter. Every machine guaranteed in perfect order. TYPEWRITERS SOLD, RENTED, EXCHANGED. Sent anywhere with privilege of examination. Send for illustrated catalogue.

National Typewriter Exchange, 214 La Salle St., Chicago.

SHORTHAND TYPEWRITER
Is superseding stenography. One stroke prints an entire word in legible English. No study, no mistakes, great speed. Anderson, 725 B. Street Building, New York

MODELS SECRECY GUARANTEED. Equipped for all classes of work. J. C. SEY L, 181 Madison St., CHICAGO

Experimental Pattern and Model Work, Optical, etc., instruments, bicycle sundries. EMPIRE NOVELTY WORKS, 402 E. 30th St., New York.

SPECTACLES F. E. BAILEY sells for new optical catalogue. 271 Wabash Ave., Chicago.

Wanted to Manufacture Small Metal Articles. Press work a specialty. Nickel plating and enameling. Correspondence solicited. J. J. Walsh Mfg. Co., Yonkers, N.Y.

FILMS & MACHINES FOR ANIMATED PHOTOGRAPHS

ICE MACHINES, Corliss Engines, Brewers' and Bottlers' Machinery. THE VILTER MFG. CO., 899 Clinton Street, Milwaukee, Wis.

EXPERIMENTAL WORK AND MODELS Special machinery, tools and dies. Secrecy guaranteed. H. ROBINSON & CO., 206 Center Street, New York City

TYPE WHEELS, MODELS & EXPERIMENTAL WORK. SMALL MACHINERY NOVELTIES ETC. NEW YORK STENCIL WORKS 100 NASSAU ST. N.Y.

FOR SALE Valuable Patent. Improved Potato Digging Machine. Will do more and better work than any machine in market. For particulars addr. Carl Hartman, 5 Maspeth Ave., Brooklyn, N.Y.

Experimental & Model Work Ours and advice free. Gardam & Son, 45-51 Rose St., N.Y.

STRONG CASTINGS. QUICK DELIVERY. PATTERN WORK TO ORDER. ACME MALLEABLE IRON WORKS, BUFFALO, N.Y.

WOOD WORKERS BUCK BROS. CAST STEEL BUCK BROS. Millbury, Mass.

RAMS The Double Acting Rams open the valves as well as shut them off with the power of the water. More water raised in proportion to waste than any ram made. No stopping. C. Hodgkins & Sons, Marlboro, N. H.

The Only Pure Water ABSOLUTELY aerated with sterilized air, is made by **THE SANITARY STILL.** Made of copper, lined with block tin, easily cleaned, simple as a teakettle, fits on any gas, oil, wood or coal range. Four Styles, \$10.00, \$11.50, \$13.50 and \$15.00. Satisfaction guaranteed or money refunded. Booklet free—tells what The Sanitary Still has done for others and will do for you. Distilled water preserves health and prevents disease. Endorsed by all physicians and 3,000,000 Rats tonites. **THE CUPRIGRAPH CO** 90 N. Green Street, Chicago.

Are You Looking for Something for a PRESENT

FOR YOUR FATHER OR SON, EMPLOYER OR EMPLOYEE, TEACHER OR PUPIL, LIBRARY OR READING ROOM? HERE IT IS!

Experimental Science

By GEO. M. HOPKINS.

17th Edition Revised and Enlarged.

840 pages, 782 fine cuts, substantially and beautifully bound. Price in cloth, by mail, \$4. Half morocco, \$5.

This splendid work gives young and old something worthy of thought. It has influenced thousands of men in the choice of a career. It will give anyone, young or old, information that will enable him to comprehend the great improvements of the day. It furnishes suggestions for hours of instructive recreation.

Send for large illustrated circular and complete table of contents.

MUNN & CO., Publishers, Office of the . . . SCIENTIFIC AMERICAN, 361 BROADWAY, - NEW YORK.

AMERICAN DESK \$33.33 DELIVERED STUOL CO. EAST OF THE MISSISSIPPI 60 inches long SEND FOR CATALOGUE

PROJECTING NOVELTIES "VIVE MARVEL" In One "GRAPHOSCOPE" \$75.00. Complete Picture Machine. PHOTOGRAPHS, GRAPHOPIQUES, RECORDS, FILMS. Also MAGIC LANTERNS WANTED OR FOR SALE HARBACH & CO. 809 Filbert St. Phila. Pa.

Are you interested in acetylene carbide, gas engines, coal, coke, petroleum, gas, water, electricity or chemistry, or engineering generally? If you are, send two cent postage stamp to **PROGRESSIVE AGE**, 280 Broadway, New York, and get list of valuable articles prepared by some of the most eminent writers of the time on these and many other technical subjects. Synopsis accompany title, and will enable you to judge character of same and whether you wish copy.

Invalid's Home Healer

ELECTRICITY, the great curative agent, is used by successful physicians in the treating of Nervous, Muscular and various other ailments. Many diseases will yield to no other treatment.

This **ELECTRO-MAGNETIC MACHINE** is the result of combining Medical Science with Mechanical Genius. **DR. CUTTEN** evolved a compact and simple instrument from the complicated and expensive apparatus ordinarily used, eliminating faults yet retaining qualities. It is intended for medical use, and for this purpose has far surpassed the hopes of its inventor, and places within reach of all the benefits of **HOME TREATMENT**.

For those who cannot afford an expensive course of electrical treatment, this Dynamo will prove a great boon. It develops without shock or irritation, a strong and continuous **DIRECT CURRENT** (not alternating) essential to the best curative results.

This **HOME HEALER** is always ready for instant use, no physician's prescriptions are necessary, no chemicals, a child can operate it.

The current may be accurately gauged to the needs of the patient, mild or strong, and is effectively distributed through the system by means of electrodes which may be applied to any part of the body. **STRONG, SIMPLE AND EFFECTIVE.** Will last for years.

A Wonderful Electrical Novelty.


This Hand Dynamo may also be run as a motor by connecting four or five cells of any kind of Battery. It may be used for electroplating, running small incandescent lamps, ringing magnet bells, running small experimental machines, etc.

The Dynamo comprises permanent field magnet and armature connected with multiplying gear giving great speed, switch for controlling current and conductor cords attached to electrodes, mounted on polished wood base. **DR. CUTTEN'S TREATISE** on **ELECTRIC HEALING**, giving explicit directions for home use, free with each dynamo.

PRICE \$1.00.

BY MAIL, \$1.20.

ROBT. H. INGERSOLL & BRO., 65 CORTLANDT ST., Dept. 147, NEW YORK



Advertisements.

ORDINARY RATES.


Inside Page, each insertion, - 75 cents a line
Back Page, each insertion, - \$1.00 a line

For some classes of Advertisements, Special and Higher rates are required.

The above are charges per agate line—about eight words per line. This notice shows the width of the line, and is set in agate type. Engravings may head advertisements at the same rate per agate line, by measurement, as the letter press. Advertisements must be received at Publication Office as early as Thursday morning to appear in the following week's issue.

Cribune & Bicycle

Tested and True.



The Easiest Running Wheel in the World.
Send for Catalogue.

THE BLACK MFG. CO., ERIE, PA.

THE BICYCLE: ITS INFLUENCE IN Health and Disease.—By G. M. Hammond, M.D. A valuable and interesting paper in which the subject is exhaustively treated from the following standpoints: 1. The use of the bicycle by persons in health. 2. The use of the bicycle by persons diseased. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 1002. Price 10 cents. To be had at this office and from all newdealers.


The Remington Standard Typewriter

does, and always has done, the Best Work for the longest time, with the least effort on the part of the operator, and the least expense to the owner.



New Models now better than ever before

Wyckoff, Scamans & Benedict,
327 Broadway, New York.



FACTORIES

are appreciating the Charter Gas and Gasoline Engine

Proof from nearly every State and Territory of the Union, by addressing
CHARTER GAS ENGINE CO., Box 148, STERLING, ILL.



GARDNER GRINDER

FOR FLAT SURFACES
ACCURATE RAPID
CHESLEY & CO. CHICAGO-ILL. U.S.A.

Way You Like


either horizontally or vertically. That's the great



VAN NORMAN "DUPLEX" MILLING MACHINE.

It saves time, tools, and fixtures, and will be found a boon in every up-to-date shop. Produces the most accurate work. Simple, serviceable, and satisfactory in every way. Waltham Watch Tool Co., Springfield, Mass.

A PAINTING MACHINE



Turner Machine Co., 37 West 14th St., New York City.

.50% Carbon Pioneer Brand Steel Tube

Every Bicycle Manufacturer should use it.
Every Dealer should insist on having it.
Every Rider should demand it.



While WEIGHT FOR WEIGHT in a Bicycle our FIFTY CARBON Steel will last so long

and TWENTY-FIVE CARBON Steel will last only so long

NOTE THE FULL IMPORT OF THE PARALLEL LINES.

The comparison which they graphically make indicates the result of the prolonged investigations of the most practical experts of the world. That the tests in our own laboratory corroborate these results is merely so much to its credit; that the same is true of actual trial on the road equally proves the trial to have been made in bicycles of correct design and construction. THE FACT REMAINS UNDISPUTED.

The Margin of Safety is Greatly Increased by the Use of this Tube.

Send for Catalogue. THE POPE TUBE CO., HARTFORD, CONN.

THOROUGH INSPECTIONS
AND
INSURANCE
AGAINST LOSS
OR
DAMAGE
TO
PROPERTY
AND
LOSS OF LIFE
AND
INJURY
TO PERSONS
CAUSED BY
STEAM-BOILER-EXPLOSIONS
J. M. ALLEN, PRESIDENT
W. B. FRANKLIN, VICE PRESIDENT
J. B. PIERCE, SECRETARY
F. B. ALLEN, 2ND VICE PRESIDENT

HOW to make money with a Magic Lantern or Stereopticon is explained in 250-page catalog describing apparatus & Views free. McALLISTER, Mfg. Optician, 49 Nassau St., N. Y.

IMPERIAL BALL BEARING AXLE

A written guarantee with each set of axl s.

97 PATTERN

8,000 sets in use.

Indorsed by the leading carriage builders.

Reduces friction 75 per cent. One horse can do the work of two. Mechanically perfect. Can be put on old or new work.

Write for our Illustrated Catalogue and Testimonials, which we send free on application. Imperial Ball Bearing Axle Dept., 439 Wabash Avenue, Chicago, Ill.

OUR 1898 CHAMPION BICYCLE HUBS. . . .

Bearings are correct shape to give true rotation to balls without slip. Cones are warranted tool steel, thoroughly hardened, ground, and polished dead true. Write for Circular. I. A. WESTON CO., Syracuse, N. Y., Manufacturers of Cycle Wheels, Sulky Wheels, Carriage Wheels, Crank Hangers, Bicycle Hubs, Spokes, Nipples, Rims, Balls, etc.

HARRINGTON & KING PERFORATING
WE CAN DELIVER RAPIDLY PERFORATED SHEET-METALS
OF EVERY DESCRIPTION
NAME THICKNESS OF METAL, SIZE AND SHAPE OF HOLE
225 NORTH UNION ST. CHICAGO, ILL. U.S.A.

Geography Becomes

real experience if the children see, vivid on the screen, the scenes described in the text book. One good life sized view of a Bushman in war costume will fix the facts about Australia more firmly in their heads than any amount of description. A Stereopticon is not very dear, and we rent at very low rates all imaginable kinds of slides. Hire lists free.

RILEY BROTHERS,

Bradford, Eng. 16 Beekman St., New York

The Largest Stereopticon Outfitters in the World.

BRANCHES—BOSTON: 36 Bromfield St. CHICAGO: 69

Washington St. KANSAS CITY, MO.: 515 East 14th

St. MINNEAPOLIS: 22 Washington Ave. So.

DORMAN'S VULCANIZERS

are used all over the world.

Exclusive Manufacturers of Steam Machines for Rubber Stamps. We also make Dry Heat Vulcanizers. Complete outfits from \$10 to \$1,000. All Stamp and Stencil Tools and Supplies. Brass and Steel Dies for all purposes. Scales, Engraving and Die Sinking of all kinds. Established 1860. Printing Presses, with complete outfits, from \$1 to \$100. Send for Catalogues.

THE J. F. W. DORMAN CO., 121 E. Fayette St., Baltimore, Md., U. S. A.

HALF A CENTURY OF CYCLES.—AN interesting history of the cycle from its origin up to the present time. The first crank-driven bicycle. The "boneshaker" and its successors. The tricycle. The modern wheel. Cycle building a science. Points of improvement. The pneumatic tire. A hand and foot cycle. With 9 illustrations. Contained in SCIENTIFIC AMERICAN SUPPLEMENT, No. 1012. Price 10 cents. To be had at this office and from all newdealers.

IT COSTS NOTHING TO TRY!
All steam users can save time money and trouble with the simplest, safest and most satisfactory trap in existence—the HEINTZ STEAM TRAP. Guaranteed never to wear out. Look at the cut and see how it's done! Pay me what you save in coal for one year and I'll furnish the trap free. See illus. notice Sci. Am. July 13, 1897. Sole American Mfr. Wm. S. Haines, 8 136 S. 4th St., Phila., Pa.

SO SIMPLE A CHILD CAN USE THEM

SUNART MAGAZINE CAMERAS.

Folding Cameras. All sizes, ranging in price from \$5 to \$100. Sunart Junior, 3 1/2 x 3 1/2 picture, \$5.

Send 2 cent stamp for Illustrated Catalogue.

SUNART PHOTO CO.

5 AQUEDUCT STREET, ROCHESTER, N. Y.

A FOLDING CAMERA.—WORKING

Drawings showing how to build a folding camera. A practical paper by an amateur for amateurs. 4 illustrations. Contained in SUPPLEMENT 1021. Price 10 cents. For Sale by Munn & Co. and all newdealers.

The Typewriter Exchange

1 1/2 Barclay St., NEW YORK

156 Adams St., CHICAGO

38 Court Square, BOSTON

81 B Wyandotte St., KANSAS CITY, MO.

We will save you from 10 to 50% on Typewriters of all makes.

Send for Catalogue

At 1/4 Price

Bicycles, Watches, Guns, Buggies, Harness, Sewing Machines, Organs, Pianos, Safes, Tools, Scales of all varieties and 1000 other articles. Lists free. CHICAGO SCALE CO., Chicago, Ill.

SCREW-CUTTING DIE HEADS

SELF-OPENING AND ADJUSTABLE.

The best die head on the market. Some advantages over "others." viz.: They are smaller, stronger, more compact, have no levers to spring, cannot be clogged by chips, are always reliable, and the prices are right. Send for descriptive circular "S. A." Our die heads are furnished in sizes suitable for cutting threads from No. 10 wire gauge to 6 inches diameter inclusive.

GEOMETRIC DRILL CO., WESTVILLE, CT.

EUROPEAN AGENTS: WHITE, CHILDS & BENNY, Vienna, Austria.

"It Tells About Tools"

Every Mechanic, Metal Worker, or person interested in Machinery Supplies should have our new 1897 Tool Catalogue. It contains 710 pages, size 10 1/2 x 7 1/2, and is an exhaustive and instructive list of all tools that may be required. Handsomely bound in cloth, express paid on receipt of \$1. Money paid for book will be refunded with first order amounting to \$10 or over. Send stamps or money order.

MONTGOMERY & CO.

MAKERS OF JOBBERS IN FINE TOOLS,

105 Fulton Street, New York City.

Don't Be Persuaded

into paying a high price for a Swiss watch. Waltham Watches are the most accurate made. The "RIVERSIDE" movements particularly recommended.

For sale by all retail jewelers.

GUNDLACH OPTICAL CO.
761-765 S. CLINTON ST.
ROCHESTER, N. Y.
MANUFACTURERS OF PHOTOGRAPHIC APPARATUS.
OUR NEW CYCLE OUTFIT CAN'T BE BEATEN FOR QUALITY OR PRICE.

INSTRUCTION AND AMUSEMENT

It's the new fad in schools to teach children by means of Magic Lantern Exhibitions, thus teaching by the eye as well as the mind. We have 30,000 Lantern Slides to select from. Also Oil Light Lanterns, Oxy-Hydrogen, Acetylene, and Electrical Lanterns.

Send for catalogue to C. T. MILLICAN, Philadelphia, Pa.

730 Chestnut Street,

FISCHER'S

CIRCLE

DIVIDER AND ANGLE PROTRACTOR

This instrument divides a circle into as many parts as there are eighths or sixteenths of an inch in its radius, by means of the points, which are marked "8" and "16". It is a very useful and time-saving novelty.

Instrument in cloth covered pocket case, with directions, post paid \$1.50. KEUFEL & FISCHER CO., Manufacturers, 44 Ann Street, New York.

JESSOP'S STEEL

THE VERY BEST FOR TOOLS, SAWS, ETC.

WM. JESSOP & SONS, 91 JOHN ST. NEW YORK

Buy Telephones

THAT ARE GOOD—NOT "CHEAP THINGS."

The difference in cost is little. We guarantee our apparatus and guarantee our customers against loss by patent suits. Our guarantee and instruments are both good.

WESTERN TELEPHONE CONSTRUCTION CO.

250-254 South Clinton St., Chicago.

Largest Manufacturers of Telephones exclusively in the United States.

Every Scientist

should subscribe for the

Scientific American

He cannot afford to be without it any more than the doctor can dispense with the Materia Medica. It is the leading scientific publication of the world and is everywhere acknowledged as the standard authority on every subject pertaining to science in all branches. It consists of sixteen large pages, profusely illustrated, and contains articles by the most eminent writers on the mechanical arts. It is a weekly record of new patents and inventions, and is indispensable to every person who is interested in the progress and improvement of manufactures and means of manufacture.

\$3 00 a year, \$1 50 for six months. For sale by all newdealers. Remit by check, draft, express or money order.

MUNN & CO., Publishers,

361 Broadway, New York City.

ANTI-RUSTINE

Prevents Rust on Machinery and Tools.

GOLDING & CO. BOSTON, MASS.

PRINTING INKS

The SCIENTIFIC AMERICAN is printed with CHAS. ENEB JOHNSON & CO.'S INK, Tenth and Lombard Sts., Philadelphia, and 47 Rose St. opp. Duane, New York

No. 76.



GIVE US YOUR CONFIDENCE

A million M. & G. Knives are to-day in use. You are unjust to us not to try us. Every blade is hand forged razor steel, file tested, warranted. Knife at left, No. 76, ivory handle, 3 blades, \$1 post paid; with two blades, 75 cents. Stronger two blade shop knife, 75 cents. Cut at right, "Our Masterpiece," No. 34; price, with ebony handle, \$1.25; ivory, \$1.50; richest pearl, \$2. 8 in. razor steel Shears, 75 cents. Hol- low ground Razor, with Strip, \$1.50. Send for illustrated 80 page free List and "How to Use a Razor."

MAHER & GROSH CO., 40 A STREET, TOLEDO, OHIO.

No. 34.

